

BASIS OF BEARING

Geodetic North at the Southwest corner of Section 33,
Township 3 North, Range 39 East of the Willamette
Meridian, as determined by GPS observation

SCALE: 1" = 500'

LEGEND

- Found 2 1/2" aluminum pipe with 2 1/2" aluminum cap marked as per Union County Monumentation records, set by Survey Number 065-2015
- ⊙ Found 5/8" iron pin, set by Survey Number 108-77
- Found 5/8" iron pin with 2 1/2" aluminum cap, marked as per Union County Monumentation records, set by Survey Number 025-2014
- Found 5/8" iron pin set by Survey Number 82-78
- ⊙ Found 5/8" iron pin with 2" aluminum cap, set by Survey Number 041-1996
- Found 5/8" iron pin with 2 1/2" aluminum cap, set by Survey Number 024-2017
- ⊙ Set 5/8" x 30" iron pin with 2 1/2" aluminum cap, marked as per Union County Monumentation records, filed separately (unless otherwise noted)
- () Record measurement as per Survey Number 025-2014
- [] Record measurement as per Survey Number 108-77
- / / Record measurement as per Survey Number 82-78
- Steel fencepost set on line

REFERENCE MATERIAL

Union County Monumentation Records
Survey Number 108-77
Survey Number 82-78
Survey Number 041-1996
Survey Number 025-2014
Survey Number 065-2015
Survey Number 024-2017

Field Notes of GLO contract no. 382, dated March 23, 1881, executed by Rufus S. Moore

DEED REFERENCES

Microfilm Document Number 20134274
Microfilm Document Number 20134269

NARRATIVE

This survey was done at the request of Patrick Marolla, on behalf of Hancock Forest Management, land manager for the land within. Mr. Marolla wanted the ownership lines monumented and posted. I recover the monuments as shown. Finding them harmonious with record measurements, I accept them in place. Subdivision of sections was done as per BLM Manual of Instructions 2009. Fencelines are off as shown. I find no unusual conditions with this survey.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JUNE 2, 2010
JEFFREY S. HSU
83571

Renewal Date: June 30, 2019

UNION COUNTY
SURVEYOR

Date Received 12/14/17

Date Filed 12/14/17

By J. S. H.

File No. 049-2017

BAGETT, GRIFFITH & BLACKMAN

2006 Adams Avenue, LaGrande, Oregon
Map of Survey

Situate in Sections 22, 23 and 27 of Township 2
North, Range 39 East of the Willamette Meridian

| | |
|----------------------|------------------------------|
| UNION COUNTY, OREGON | |
| SURVEYED FOR | Hancock Forest Management |
| SURVEYED BY | J. S. H. |
| Scale: 1" = 500' | Drawn by: J. S. H. Dec. 2017 |

SURVEY NUMBER 049-2017

