

BASIS OF BEARING

The West line of the Southwest quarter of Section 25, Township 3 North, Range 39 East of the Willamette Meridian being South 0°32'41" East, as per Union County Survey Number 026—2008

SCALE: 1"=500'

LEGEND

Found monument as described, marked as per Union County Monumentation record

 \odot

0

- Found 5/8" iron pin, set by Survey Number 49—71
- Found 5/8" iron pin set by Survey Number 14–85
- Found 5/8" iron pin with aluminum cap marked BGB SURVEY MARKER "RP" set by 023-2016
 - Set 5/8"x30" iron pin with 1 1/2" aluminum cap marked UNION COUNTY SURVEYORS
- Set 5/8"x30" copper clad iron pin with 2 1/2" brass cap in concrete, marked as per Union County Monumentation record, filed separately
- () Record measurement as per field notes of GLO contract no. 498 executed by F.W. Campbell
- Record measurement as per Union County
 Monumentation record 33—85R and Survey 14—85
- Record measurement as per Survey No. 017—2005
- Record measurement as per Survey No. 023—2016

Centerline

REFERENCE MATERIAL

Union County Monumentation Records
Survey Number 49—71
Survey Number 77—71
Survey Number 14—85
Survey Number 017—2005
Survey Number 026—2008
Survey Number 023—2016
Survey Number 043—2017

Field notes of GLO contract No. 498 executed by F.W. Campbell dated March 10, 1884

Road Petition Number 667

NARRATIVE

This survey was done at the request of the Union County Surveyor. The purpose is to monument corner positions established by surveys 14–85 and 023–2016 that were not set due to ongoing road construction. References for the set monuments were put in place before construction on the road. I establish the corner positions by record distance from said reference monuments. I find no unusual conditions with this survey.



UNION COUNTY
SURVEYOR

Date Received 1/24/18

By 6/16

File No. 002-2018

BAGETT, GRIFFITH & BLACKMAN 2006 Adams Avenue, LaGrande, Oregon Map of Survey

Situate in Section 36, Township 3 North, Range 39 East of the Willamette Meridian

UNION COUNTY, OREGON		
SURVEYED FOR	Union County Surveyor	
SURVEYED BY	J. S. H.	
Scale: 1" = 500	o' Drawn by: K. A. T.	January 2018