

Brock Eckstein, City of Elgin

# BASIS OF BEARING

Solar observation taken at the North quarter corner of Section 15, Township 1 North, Range 40 East of the Willamette Meridian.

SCALE: 1"=30'

## LEGEND

- Found 5/8" iron pin with yellow plastic cap marked BGB SURVEY MARKER, set by Survey Number 028-1998
- Set 5/8" iron pin with yellow plastic cap marked BGB SURVEY MARKER



Portion to accrue to Pacheco

#### REFERENCE MATERIAL

Plat of Thompson's Addition Survey Number 028-1998

DEED REFERENCES Microfilm Document Number 20122896 20163297 20163893 Book 99, Page 547

Circuit Court Case 98-10-39025

### NARRATIVE

This survey was done at the request of Patricia Pacheco, owner of the land within. Ms. Pacheco wanted to adjust her East line to resolve a garage, shed and driveway encroachment. I place the lines as per Survey Number 028-1998. The portion in the Northwest of the Pacheco property was awarded to Smolkowski by Circuit Court Case 98-10-39025. Microfilm Number 20163893 attempts to use a abridged legal description for this portion which is incorrect. For legal descriptions prepared with the adjustment, I use the legal description as per court case.

The NE corner of the Pacheco property prior to adjustment falls directly underneath the wall of the garage, and I reset the pin at the centerline of the alley to serve as a witness corner. True corner position is 2.8 feet South, as per said court case.

As the Kepplinger property commences at the Southeast corner of Block 4 of Thompson's Addition, I place the right of way of Alder Street in common with the location of Alder Street as per Thompson's Addition. For purposes of this survey, I drive the centerline at the East end of Alder in Thompson's Addition to the intersection of 15th and Alder, established by a concurrent survey for the City of Elgin. Though it is shown this way on this survey, I will disclaim that the area between Thompson's and Hindman's Addition is an area that is fraught with ambiguity due to conflicting points of beginning. An ODOT survey, filed as 045-2003, indicates a differing potential location for the Alder Street East of Thompson's Addition. Though the focus of that particular survey was to place Division Street. It is for these reasons that a true and accurate location of the title line between Kepplinger and Smolkowski is beyond the scope of this survey.

I find no unusual conditions with this survey.

REGISTERED **PROFESSIONAL** LAND SURVEYOR OREGON JEFFREY S. HSU 83571

#### **№** BAGETT, GRIFFITH & BLACKMAN 2006 Adams Avenue, LaGrande, Oregon

Map of Survey Situated in the Northeast quarter of the

Southwest quarter of Section 15, Township 1 North, Range 39 East of the Willamette Meridian, City of Elgin UNION COUNTY, OREGON

Patricia Pacheco SURVEYED FOR J. S. H. SURVEYED BY Scale: 1'' = 30'Drawn by: J. S. H. June 2018