

This survey was done at the request of Patrick Marolla, on behalf of Hancock Forest Management, land manager for the land within. Mr. Marolla wanted the ownership lines monumented. I recover the monuments as shown. The Center West 1/16th corner was originally set by Survey 034—1995. The monument shows evidence of having been removed and reset at an incorrect location as all the other monuments set by said survey are harmonious with record. I reestablish this position at record angle and distance from the other monuments set by said survey. The tie to the fence from said survey matches the position from the reset CW 1/16th corner. There was a boundary line agreement for the first 138.07 feet North of the Center—West 1/16th corner, filed as Microfilm 962139, as no section subdivision was done at the time. In the language of the boundary line agreement, it states that each party agrees on the accuracy of the pins "notwithstanding the results of any future surveys in the area". Between the true aliquot line and the boundary line agreement line, there is a 0.59 foot discrepancy at the North end of the 138.07 foot section, tapering to nothing at the Center—West 1/16th location. Subdivision of section was done as per BLM Manual of Instructions 2009. I find no unusual conditions with this survey.

BAGETT, GRIFFITH & BLACKMAN 2006 Adams Avenue, LaGrande, Oregon Map of Survey Situate in The North West Quarter of Section 13 of Township 2 North, Range 39 East of the Willamette Meridian UNION COUNTY, OREGON SURVEYED FOR Hancock Forest Management SURVEYED BY J. S. H.

Scale: 1" = 300'

May 2019

Drawn by: J. S. H.