



BASIS OF BEARING

The North line of Section 35, Township 4 South, Range 38 East of the Willamette Meridian being South 89°46'53" West, as per Survey Number 015-2003

SCALE: 1"=200'

LEGEND

- ⊙ Found 2 1/2" x 30" aluminum pipe with 2 1/2" aluminum cap, marked as per Union County Monumentation records, set by Survey Number 015-2003
- ⊙ Set 2 1/2" x 30" aluminum monument at position of found stone
- x— Existing fence line
- Set steel fence posts on line
- () Record information as per field notes of GLO Contract Number 388, executed by W.B. Barr

REFERENCE MATERIAL

Original GLO Contract Number 388 by W.B. Barr dated May 7, 1881
 Union County monumentation records Survey Number 015-2003
DEED REFERENCES
 Microfilm Document Number 20134270
 Microfilm Document Number 962599

NARRATIVE

This survey was done at the request of Patrick Marolla, on behalf of Hancock Forest Management, land manager of the land within. Mr. Marolla wanted lines posted in preparation for a timber sale. I recover monuments as shown. I find the original stone at the quarter corner position, its original position verified with accessories. I remonument the stone position. I find no unusual conditions with this survey.

HANCOCK

BOOTHMAN RANCHES

REGISTERED PROFESSIONAL LAND SURVEYOR
 OREGON JUNE 2, 2010
 JEFFREY S. HSU 83571
 Renewal Date: June 30, 2021

UNION COUNTY SURVEYOR
 Date Received 8/20/19
 Date Filed 8/20/19
 By MGB
 File No. 023-2019

BAGETT, GRIFFITH & BLACKMAN 2006 Adams Avenue, LaGrande, Oregon Map of Survey		
Situate in Sections 22 and 23, Township 4 South, Range 38 East of the Willamette Meridian.		
UNION COUNTY, OREGON		
SURVEYED FOR	Hancock Forest Management	
SURVEYED BY	J. S. H.	
Scale: 1" = 200'	Drawn by: K. A. T.	Aug. 2019

SURVEY NUMBER 023-2019