

## BASIS OF BEARING

True Geodetic North at the Southeast corner of Section 36, Township 3 North, Range 40 East of the Willamette Meridian, as determined by GPS observation

SCALE: 1"=600'

## LEGEND

Set 2 1/2" x 30" aluminum pipe with 3" aluminum cap, marked as per Wallowa/Union County Monumentation Records, from original corner evidence

Set 5/8"x30" iron pin with 2 1/2" aluminum cap, marked as per Wallowa/Union County Monumentation Records, at proportionate position

Record measurement as per field notes of GLO Contract Number 382, dated March 23, 1881, executed by Rufus S. Moore

Set fence post on line

0

## REFERENCE MATERIAL

Wallowa County Monumentation Records Partition Plat 07-57303 Partition Plat 08-59267 Partition Plat 12-68406

Field notes of GLO Contract Number 382, dated March 23, 1881, executed by Rufus S. Moore

<u>DEED REFERENCES</u> Microfilm Document Number 070444

## NARRATIVE

This survey was done at the request of Patrick Marolla, on behalf of Hancock Forest Management, owner of the land within. Mr. Marolla wanted select corners set to establish property lines prior to logging. At the Southwest corner of Section 6, I find the remnants of the NW bearing tree with visible BT scribes as well as the living SW bearing tree. I find both bearing trees at the West quarter corner of Section 18, alive and vigorous. I set both monuments at record bearing and distance. I make a search for intermediate corners but find no remaining evidence. I establish their position at proportionate position. I find no unusual conditions with this survey.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JUNE 2, 2010

JEFFREY S. HSU
83571

Renewal Date: June 30, 2021

UNION COUNTY
SURVEYOR

Date Received 9/3/19

Date Filed 9/3/19

By 15/5/19

File No. 026-2019

BAGETT, GRIFFITH & BLACKMAN
2006 Adams Avenue, LaGrande, Oregon
Map of Survey

Situate in Section 12 and 13, Township 2 North, Range 40 East and Sections 7 and 18, Township 2 North, Range 41 East of the Willamette Meridian

UNION COUNTY, OREGON

SURVEYED FOR Hancock Forest Management

SURVEYED BY J. S. H.

Scale: 1" = 600' Drawn by: J. S. H. Aug. 2019