

## REFERENCE MATERIAL

### *NARRATIVE*

This survey was done at the request of Patrick Marolla on behalf of Hancock Forest Management, land manager of the land within. Mr. Marolla wanted select monuments set and lines posted prior to logging. I find monuments set by Surveys 22-86 and 031-2012 in position and harmonious with record measurements. I make a search for the North and East quarter corners of Section 33, but find no remaining evidence of the original GLO corners. The area has been heavily logged. I use the proportionate positions but do not set monuments as the area is under one ownership. Break of the section was done as per BLM Manual of Instructions 2009. I find no unusual conditions with this

Field notes of GLO Contract Number 320, dated April 1, 1879, surveyed by H.M. Thatcher

Field Notes from BLM Special Instructions, group number 350, dated May 3, 1957, executed by Stephen Albright

> Union County Monumentation Records Survey Number 22-86 Survey Number 29-88 Survey Number 031-2012 Survey Number 008-2013

> > DEED REFERENCES

Microfilm Document Number 20134272 Microfilm Document Number 20134271



# UNION COUNTY SURVEYOR 12/3/19 040-2019

BAGETT, GRIFFITH & BLACKMAN 2006 Adams Avenue, LaGrande, Oregon Map of Survey

Situated in Section 33, Township 4 South, Range 41 East of the Willamette Meridian

UNION COUNTY, OREGON Hancock Forest Management SURVEYED FOR SURVEYED BY J. S. H. Scale: 1" = 600'Drawn by: K. A. T. | Nov. 2019

# BASIS OF BEARING

The North/South Centerline of Section 30 being North 210'37" East, as per Survey Number 29—88, as filed in the office of the Union County Surveyor

SCALE: 1"=600'

- Found 2 1/2" iron pipe with 3" brass cap, set by BLM Surveyor Stephen Albright under Special Instructions, group number 350, dated May 3, 1957 and marked as per Union County Monumentation record 042-2012R
- Found 2 1/2" aluminum pipe with 2 1/2" aluminum cap marked **(** as per Union County Monumentation records, set by Survey Number 22-86
- Found 2 1/2" aluminum pipe with 2 1/2" aluminum cap marked as per Union County Monumentation records, set by Survey Number 031-2012
- Found 2 1/2" aluminum pipe with 2 1/2" aluminum cap, marked as per Union County monumentation record 046-2012R
- Set  $5/8" \times 30"$  iron pin with 2 1/2" aluminum cap marked as 0 per Union County Monumentation Records
- Searched for not found, used proportionate position, no new >< SFNF monument set
- Record measurement as per Field Notes of GLO Contract No. 320, by H.M. Thatcher, dated April 1, 1879
  - Record measurement of Survey Number 22-86
- Record measurement of Survey Number 031-2012
  - Record measurement of Survey Number 008-2013
    - Steel fencepost set on line

 $\odot$ 

SURVEY NUMBER 040-2019