



### BASIS OF BEARING

The East/West centerline of Section 21, Township 1 North, Range 38 East of the Willamette Meridian being North 86°13'28" West, as per Surveys 033-1994 and 019-1997

**SCALE: 1" = 500'**

### LEGEND

- Found monument as noted, marked as per Union County Monumentation records
- ⊙ Set 5/8"x30" iron pin with 2 1/2" aluminum cap, marked as per Union County Monumentation records, filed separately
- [ ] Record measurement as per GLO Contract No. 120, dated May 27, 1867, executed by Joseph Gray
- < > Record measurement as per Field Notes from GLO Contract No. 579, dated June 22, 1891, executed by John Kimbrell
- { } Record measurement Field Notes from GLO Contract No. 102, dated July 20, 1863, executed by Timothy Davenport
- ( ) Record measurement Field Notes from GLO Contract No. 397, dated July 14, 1881, executed by Jacob Cooper
- Steel fencepost set on line

### REFERENCE MATERIAL

- Union County Monumentation Records
- Field Notes from GLO Contract No. 120, dated May 27, 1867, executed by Joseph Gray
- Field Notes from GLO Contract No. 102, dated July 20, 2863, executed by Timothy Davenport
- Field Notes from GLO Contract No. 397, dated July 14, 1881, executed by Jacob Cooper
- Field Notes from GLO Contract No. 579, dated June 22, 1891, executed by John Kimbrell

### DEED REFERENCES

Microfilm Document Number 20134273

### NARRATIVE

This survey was done at the request of Patrick Marolla on behalf of Hancock Forest Management, land manager for the land within. Mr. Marolla wanted to have property lines monumented and marked prior to harvesting timber. I recover the monuments as shown hereon and accept them in place. I make a diligent search for the East and West quarter corners of the section, but can find no remaining evidence. I place these corners at proportionate position. Section subdivisions were done as per BLM Manual of Instructions 2009. I find no other unusual conditions with this survey.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JUNE 2, 2010  
JEFFREY S. HSU  
83571

Renewal Date: June 30, 2021

UNION COUNTY  
SURVEYOR

Date Received 5/12/20

Date Filed 5/12/20

By J. S. H.

File No. 015-2020

**BAGETT, GRIFFITH & BLACKMAN**  
2006 Adams Avenue, LaGrande, Oregon  
Map of Survey

Situate in Section 1, Township 1 North,  
Range 38 East of the Willamette Meridian

UNION COUNTY, OREGON

SURVEYED FOR	Hancock Forest Management
SURVEYED BY	J. S. H.
Scale: 1" = 500'	Drawn by: J. S. H. May 2020