BASIS OF BEARING True Geodetic North at the corner common to Sections 19, 20, 29 and 30, Township 1 South, Range 40 East of the Willamette Meridian, as determined by GPS observation Found 2 1/2" aluminum pipe with 3" aluminum cap, set by BLM remonumentation survey, included under group #1000 special instructions dated July 13, 1979, executed by Scott McIntyre and recorded as SCALE: 1"=500' Union County monumentation record 801-84R 2657. Found monument as described, as per Union County \odot Monumentation Records Set 2 1/2"x30" aluminum pipe with 3" aluminum cap marked as per Union County Monumentation records, filed separately Fenceline Record measurement as per Field Notes for GLO Contract No. 102, executed by Timothy Davenport, dated July 20, 1863 *HANCOCK* 25|30REFERENCE MATERIALUnion County Monumentation Records BLUE CREEK Union County Survey Records Partition Plat Number 20130003T EASTEAST BLM Remonumentation Survey, under special instructions dated July 13, 1979, under Group Number 1000, executed by Scott McIntyre Field Notes for GLO Contract No. 102, executed by Timothy Davenport, dated July 20, 1863 **DEED REFERENCES** Microfilm Document Number 20134269 Microfilm Document Number 20134274 RA RA Microfilm Document Number 20134272 *NARRATIVE* This survey was done at the request of Patrick Marolla on behalf of 25 30 Hancock Forest Management, land manager for the land within. Mr. Marolla wanted select monuments set prior to logging. I make a diligent search for the section corner as well as the 1/4 section corner and find no evidence of either. I set new monuments at single proportion as per BLM Manual of Instruction. I find no unusual conditions with this survey. REGISTERED **PROFESSIONAL** LAND SURVEYOR **HANCOCK** OREGON SILVER MTN. JEFFREY S. HSU 83571 Renewal Date: June 30, 2021 UNION COUNTY SURVEYOR Found 2 1/2" iron pipe with 2 1/2" brass cap, set by James Hambleton in Union County monumentation record 016-2020 BAGETT, GRIFFITH & BLACKMAN 2006 Adams Avenue, LaGrande, Oregon Map of Survey Situate in Section 25 and 36, Township 1 South, Range 39 East and Sections 30 and 31, Township 1 South, Range 40 East, of the Willamette Meridian UNION COUNTY, OREGON SURVEYED FOR Hancock Forest Management J. S. H. SURVEYED BY May 2020

Drawn by: K. A. T.

Scale: 1" = 500'