

Union County Monumentation

18 records

(79.72 chs)

S89°57'57"E

2 1/2" aluminum pipe with 2 1/2" aluminum cap, marked as per Union County Monumentation

BASIS OF BEARING

Geodetic North at the corner of Townships 1 and 2 South, Ranges 38 and 39 East, as determined by GPS observation

SCALE: 1"=1000'

LEGEND

- Found monument as described, marked as per Union County Monumentation Records
- Set 5/8" x 30" iron pin with 2 1/2" aluminum cap marked as per Union County Monumentation Records REFERENCE MONUMENTS are 5/8" iron pins with 1 1/2" aluminum caps
- O Set 5/8" x 30" iron pin with yellow plastic cap marked BGB SURVEY MARKER
- Record measurement as per field notes of GLO Contract Number 103, executed by David P. Thompson
- [] Record measurement as per Old Book Survey Page 185
- Record measurement as per Old Book Survey
 Page 355

NARRATIVE

This survey was done at the request of Dale Eisiminger and Greg Bingaman, owners of lands within this section. They wanted select property lines monumented. The area is agricultural with very few permanent lines of possession and few recorded survey work done in the area since the original GLO survey. Many of the Section lines fall along existing county roads.

Old Book Survey Page 185, by James Kimbrell surveyed along the range line in 1889. Old Book Survey Page 355 by County Surveyor Daly was done in 1913 which retraced portions of said Kimbrell survey along the East line of Section 1. The survey for Road Petition #123 for Sandridge Road specifically calls it to be along the Range line. McDonald Lane was also surveyed along the Section line. Monumentation of aliquot corners in this area have historically depended largely on the location of roads. With the lack of available monumentation and lines of possession, I find it necessary to do this as well.

Along the Range line, I hold the proportioned position between the quarter corner between Sections 7 and 12 and the Township corner for Northings. At the quarter corner position between 1 and 6, I find this falls away from the existing centerline of the road. As this road was dedicated along the range line, I hold the road centerline as the best available evidence of the original corner position and hold the centerline for Easting. A single proportion of the NE corner of Section 2 between this quarter corner and the East quarter corner of 12 falls close to the existing centerline. The distance to the Southeast corner of Section 5, T2S, R39E is very harmonious with Old Book Survey 185. Along McDonald Lane and Webster Road, single proportion of the quarter corners falls close to the existing centerlines of the roads. I place these corners as such. There are remnants of an ancient fenceline at the North quarter corner position, approximately 250 feet West and an ancient fence corner 660 feet East. I hold a single proportioned position for Easting and a line between the fence remnants for Northing. Subdivision of the section is as per BLM Manual of Instructions 2009.

There is a 60 foot strip of land in the Northeast quarter of the Northeast quarter that is not reflected in the most current deed to Insko. This appears to be an omission for the deed as there is a boundary line adjustment between Speckhart Farms and Cutberts (predecessor of the Inskos) recorded in MF 124066 that clearly reflects this. The cropline appears to follow the aliquot line however, I find no other unusual conditions with this survey.

PROFESSIONAL
LAND SURVEYOR

OREGON
JUNE 2, 2010

JEFFREY S. HSU
83571

Renewal Date: June 30, 2021

REGISTERED

SURVEYOR

Date Received 5/21/21

Date Filed 5/21/21

By 018-2021

UNION COUNTY

BAGETT, GRIFFITH & BLACKMAN 2006 Adams Avenue, LaGrande, Oregon Map of Survey

Subdivision of Section 12, Township 2 South, Range 38 East of the Willamette Meridian

UNION COUNTY, OREGON

SURVEYED FOR Dale Eisiminger/Greg Bingaman

 SURVEYED BY
 J. S. H.

 Scale: 1" = 1000'
 Drawn by: J. S. H.
 Apr-May 2021