

REFERENCE MATERIAL

Plat of Williamson's 1890 Addition to La Grande
Survey Number 97–73
Survey Number 22–78
Survey Number 023–1992
Survey Number 033–1999
Survey Number 040–2000
Survey Number 008–2021
Survey Number 18–89 (1922 monumentation of La Grande)

<u>DEED REFERENCES</u> Microfilm Document Number 20183754

NARRATIVE

This survey was done at the request of Michelle Peterson, owner of the land within. Ms. Petersen wanted to monument the exteriors of her property as well as have monuments set at the correct 'clear vision sight triangle area' as per La Grande Ordinance Section 5.6002 (B). I recover monuments as shown hereon. I base the exteriors of the block on Survey Number 023–1992. For the sight triangle, I connect points 90 feet along the centerline of the right of way, and set pins at the intersection with the property lines. I find no other unusual conditions with this survey.

BASIS OF BEARING

Forward bearing as published by the U.S.C. and G.S. from \triangle COLLEGE to \triangle VALLEY Dated 1946.

SCALE: 1"=40'

LEGEND

- Found 2" brass disc marked BAGETT GRIFFITH
 AND BLACKMAN, set by Survey Number
 008-2021
- Found 2 1/2" brass cap in valve box, set by Survey Number 040-2000
- Found 1" iron pipe, set by Survey Number 18—89 (1922 monumentation of La Grande)
- Found 5/8" iron pin with plastic cap marked

 BGA SURVEY MARKER, set by Survey Number

 023-1992
- Found 5/8" iron pin with plastic cap marked BGB SURVEY MARKER, set by Survey Number 033-1999
- O Set 5/8" x 30" iron pin with plastic cap marked BGB SURVEY MARKER

— Centerline

Sight distance line

() Record measurement as per Survey Number 18-89

Record measurement as per plat of Williamson's Addition

Record measurement as per Survey Number 023–1992

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JUNE 2, 2010
JEFFREY S. HSU
83571

Renewal Date: June 30, 2023

UNION COUNTY
SURVEYOR

Date Received 6/16/21

Date Filed 6/16/21

File No. 029-221

BAGETT, GRIFFITH & BLACKMAN 2006 Adams Avenue, LaGrande, Oregon Map of Survey Situated in Block 29, Williamson's Addition City of La Grande UNION COUNTY, OREGON SURVEYED FOR Michelle Peterson SURVEYED BY J. S. H. Scale: 1" = 40' Drawn by: J. S. H. June 2021