

ONE MILE WEST OF THE QUARRY AND A QUARTER MILE EAST OF THE QUARRY. THE BOUNDARY OF THE QUARRY OWNED BY THE STATE OF OREGON DESCRIBED IN WARRANTY DEED VOLUME 85, PAGE 529 IS DESCRIBED IN RELATION TO THE OLD HIGHWAY CENTER LINE SHOWN ON OREGON STATE HIGHWAY DRAWING 3B-11-10. TO CORRELATE THE LOCATION OF THE OLD HIGHWAY WITH THE RELOCATED HIGHWAY CENTER LINE, COMMON CENTER LINE STATIONS "WL"1635+00 P.O.T. = "O"1643+80 P.O.T. SHOWN ON SAID STATE HIGHWAY DRAWING 3B-11-10 WERE HELD. RECORD ANGLE OF 00°06'30" BETWEEN THE OLD ALIGNMENT AND THE RELOCATED ALIGNMENT FOR WALLOWA LAKE HIGHWAY WAS HELD. THE RECORD SHAPE OF THE QUARRY BOUNDARY DESCRIBED IN VOLUME 85, PAGE 529 WAS RECREATED AND POSITIONED BY HOLDING OLD HIGHWAY STATION "O"1609+84.18 P.T., 30.00 FEET LEFT OF CENTER LINE, THEN I ROTATED RECORD SHAPE TO ALIGN WITH NORTH LINE OF THE OLD HIGHWAY RIGHT OF WAY. THE RESULTING LOCATION FIT FAIRLY WELL WITH EXISTING FENCE LINES. OREGON STATE HIGHWAY DRAWING 1R-1-527 SHOWS A GOVERNMENT CORNER TIE TO THE NORTHWEST CORNER OF SECTION 10, T1N, R40E, HOWEVER NO MONUMENT WAS FOUND AT THIS LOCATION. OREGON STATE HIGHWAY DRAWING 5B-29-2 SHOWS A ROCK MOUND AT THE NORTHWEST CORNER OF SECTION 10, HOWEVER THERE ARE MULTIPLE ROCK JACKS AND A SMALL ROCK OUTCROPPINGS IN THE VICINITY AND NONE OF THEM HAD ANY MARKED STONES. THE NEAREST GOVERNMENT CORNER FOUND WAS THE WEST QUARTER CORNER TO SECTION 4, TIN, R40E.

## UNION COUNTY SURVEYOR

Date Received: 7/30/2/

File No.

OREGON JANUARY 14, 2003 BRET N. ELITHORP 63148 EXPIRES: DEC. 31, 2021

REGISTERED

**PROFESSIONAL** 

LAND SURVEYOR

Bac

Date Filed: 7/30/21 034-2021

## OREGON DEPARTMENT OF TRANSPORTATION

DEPARTME

**BOUNDARY SURVEY** CRICKET FLAT QUARRY WALLOWA LAKE HIGHWAY (OR82) UNION COUNTY, OR

**ODOT REGION 5 TECH CENTER 3012 ISLAND AVENUE** LA GRANDE, OR 97850

JULY 29, 2021 SCALE: 1'' = 100'SHEET 1 OF 1