

### BASIS OF BEARING

Geodetic North at the quarter corner common to Sections 2 and 11, T5S, R40E, Willamette Meridian, as determined by GPS observation

SCALE: 1"=500'

## LEGEND

Found monument as noted, marked as per Union County Monumentation Records

Found 3" brass cap in concrete, marked as per Union County Monumentation Records, set by Survey 16—75

Set 2 1/2" aluminum pipe monument with 3" aluminum cap marked as per monumentation record, filed separately, at record distance intersect from found original GLO bearing trees, monumentation record filed separately

Set  $5/8" \times 30"$  iron pin with 2 1/2" aluminum cap, marked as per monumentation record, filed separately

Record measurement as per GLO contract number 320, executed by H.M. Thatcher, dated April 1, 1879

Record measurement as per GLO contract number 443, executed by W.B. Barr, dated May 29, 1882

Record measurement as per Survey 043-2002

Record measurement as per Survey 16-75

Fenceline

**①** 

0

0

< >

Fence post set on line

#### REFERENCE MATERIAL

Union County Monumentation Records
Old Book Survey 360
Old Book Survey 242
Survey 030—1995
Survey 008—2013
Survey 043—2002
Partition Plat 20060020T

Field notes of GLO Contract No. 443, executed by W. B. Barr, dated May 29, 1882

Field notes of GLO Contract No. 320, executed by H.M. Thatcher, dated April 1, 1879

<u>DEED REFERENCES</u> Microfilm Document Number 20073370 Microfilm Document Number 20182594T

## NARRATIVE

This survey was done at the request of Ken Dunham, owner of the land within. Mr. Dunham wanted the property monumented and lines posted in preparation of new fencing. I recover monuments as shown hereon. Finding them harmonious with record measurements, I accept these in place. I search for the original GLO monuments that have not been remonumented and no remaining evidence at the North and South quarter corners. I find bearing trees at the West quarter corner and monument this by distance intersect from the stump remains. I break the Section as per BLM Manual of Instruction 2009. I find existing fences are off as shown. I find no unusual conditions with this survey.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JUNE 2, 2010
JEFFREY S. HSU
83571

Renewal Date: June 30, 2023

UNION COUNTY
SURVEYOR

Date Received 11/121

Date Filed 11/121

By Nel C. Nhim Deporty

File No. 050 - 2021

# BAGETT, GRIFFITH & BLACKMAN 2006 Adams Avenue, LaGrande, Oregon

Map of Survey

Situated in Section 12, Township 5 South, Range 40 East of the Willamette Meridian

UNION COUNTY, OREGON

SURVEYED FOR Ken Dunham

SURVEYED BY J. S. H.

Scale: 1" = 600' Drawn by: J. S. H. Oct. 2021