



BASIS OF BEARINGS
GEODETIC NORTH
DERIVED BY G.P.S. OBSERVATION TAKEN AT THE
CENTER-EAST 1/16 CORNER SECTION 6

SCALE: 1"=40'
40 20 0 40

I HEREBY CERTIFY THAT THIS SURVEY WAS PERFORMED AT THE
REQUEST OF THE UMATILLA NATIONAL FOREST
FOREST SUPERVISOR _____ DATE _____
Digitally signed by ERIC WATRIUD
Date: 2025.09.24 08:20:38 -0700

NARRATIVE

THIS SURVEY WAS PERFORMED FOR THE UMATILLA NATIONAL FOREST, WITH THE PURPOSE OF REESTABLISHING THE OBLITERATED CENTER-EAST 1/16 CORNER SECTION 6, T. 1 N., R. 38 E., W.M., WHICH IS A CONTROLLING CORNER ON THE NATIONAL FOREST BOUNDARY.

A SEARCH WAS MADE OF THE AVAILABLE RECORDS PERTAINING TO THIS SURVEY. IN 1980, GARY LANGLITZ, PLS #1099, SUBDIVIDED SECTION 6 DURING A SURVEY FOR THE U.S. FOREST SERVICE, UNDER CADASTRAL CONTRACT NO. 53-04R3-0-01125. SAID SURVEY WAS RECORDED AS SURVEY NO. 97-80 IN THE UNION COUNTY SURVEYOR'S RECORDS. A CORNER MONUMENTATION RECORD FOR THE CENTER-EAST 1/16 CORNER WAS FILED AS 21-84R.

DURING THE COURSE OF BOUNDARY MAINTENANCE ACTIVITIES BY FOREST SERVICE PERSONNEL, THE MONUMENT AT THE CENTER-EAST 1/16 CORNER WAS SEARCHED FOR BUT NOT FOUND. THE CORNER POSITION FALLS ON THE WESTERLY EDGE OF DRY CREEK, WHERE THE MONUMENT HAS APPARENTLY SUCCEMBED TO THE MIGRATION OF THE CREEK CHANNEL. BOTH BEARING TREES ESTABLISHED BY LANGLITZ WERE FOUND ALIVE AND IN GOOD CONDITION. ALL OTHER MONUMENTS FOUND DURING THE COURSE OF THIS SURVEY WERE ACCEPTED, AS SHOWN HEREON.

I DECLARE THE CENTER-EAST 1/16 CORNER OBLITERATED, AND REESTABLISHED IT BY DISTANCE-DISTANCE INTERSECTION FROM THE TWO FOUND BEARING TREES. TWO REFERENCE MONUMENTS WERE ESTABLISHED ALONG ALIQUOT LINES AT SAFE DISTANCES FROM THE EDGE OF THE CREEK TO HELP PERPETUATE THE CORNER, AS SHOWN HEREON.

SEE THE CORNER MONUMENTATION RECORD FILED SEPARATELY FOR MORE DETAILS REGARDING THIS CORNER AND ITS ACCESSORIES.

LEGEND

● FOUND 2" IRON PIPE WITH 2 1/2" BRASS CAP SET BY GARY LANGLITZ, PLS #1099. SEE SURVEY NO. 97-80 FILED IN THE UNION COUNTY SURVEYOR'S OFFICE AND SEE ASSOCIATED CORNER MONUMENTATION RECORD AS NOTED

○ SET A 2 1/2" X 30" ALUMINUM PIPE WITH 3/4" USFS ALUMINUM CAP MARKED AS SHOWN - SEE CORNER MONUMENTATION RECORDS FILED SEPARATELY FOR MORE DETAILS

[] RECORD BEARING AND DISTANCE FROM SURVEY NO. 97-80

XX-84R UNION COUNTY CORNER MONUMENTATION RECORD

////// NATIONAL FOREST BOUNDARY POSTED IN 1980 WITH STEEL POSTS WITH PROPERTY BOUNDARY SIGNS ATTACHED, WHICH WERE MAINTAINED THIS SURVEY

NFSL NATIONAL FOREST SYSTEM LAND

REFERENCES

UNION COUNTY SURVEYS:
SURVEY NO. 97-80

UNION COUNTY MONUMENTATION RECORDS:
3-84R, 20-84R, 21-84R, 22-84R, & 34-84R

UNION COUNTY DEED RECORDS:
DOCUMENT NO.'S 20140893, 20161306, & 20163615

UNION COUNTY SURVEYOR	
Date Received	9/29/25
Date Filed	9/29/25
By	JLH
File No.	036-2025



UNITED STATES DEPARTMENT OF AGRICULTURE FOREST SERVICE		
REGION 6 - NORTHEAST OREGON LAND ZONE 1550 DEWEY AVENUE, SUITE A - BAKER CITY, OREGON 97814 - (541) 523-1283		
MAP OF SURVEY REESTABLISHMENT OF THE CENTER-EAST 1/16 CORNER SECTION 6, T.1N., R.38E., W.M., UNION COUNTY, OREGON		
SURVEYED FOR	UMATILLA NATIONAL FOREST	
SURVEYED BY	JLH	SURVEY COMPLETED: 8/28/2025
SCALE: 1"= 40'	DRAWN BY: JLH	

SURVEY NUMBER 036-2025