



BASIS OF BEARING

Forward bearing as published by the U.S.C. and G.S. from Δ COLLEGE to Δ VALLEY Dated 1946.

SCALE: 1"=50'

LEGEND

- ⊙ Found 1 1/2" brass disc in concrete, set by Survey Number 009-2012
- ⊙ Set a 2" brass cap marked BGB SURVEY MARKER in 4" collar of concrete in place of found 3/4" iron pipe, set by Survey 18-89 (1922 monumentation), tied prior to paving
- Found brass screw in lead plug with brass washer marked OPLS 83571, set by Survey 009-2012 or 012-2013
- Found 2" brass disc in concrete, set by Survey Number 012-2013
- Found 5/8" iron pin set by Survey Number 92-74
- Found 5/8" iron pin with yellow plastic cap marked BGB SURVEY MARKER set by Survey Number 006-2026
- ⊙ Set 5/8" x 30" iron pin with 2" brass cap marked BGB SURVEY MARKER set in 4" collar of concrete
- Set brass screw in lead plug with brass washer marked OPLS 83571
- ◻ Set cotton spindle in asphalt for reference
- ⊕ Manhole
- Centerline
- () Record measurement as per Survey Number 18-89
- { } Record measurement as per Survey Number 009-2012
- ~ ~ Record measurement as per Survey Number 012-2013
- [] Record measurement as per Survey Number 006-2026

REFERENCE MATERIAL

- Survey Number 17-64
- Survey Number 99-73
- Survey Number 68-74
- Survey Number 68-74
- Survey Number 18-89 (1922 monumentation of La Grande)
- Survey Number 009-2012
- Survey Number 012-2013
- Survey Number 006-2026
- Plat of CHAPLIN'S ADDITION

NARRATIVE

This survey was done at the request of Kyle Carpenter, Public Works Director for the City of La Grande. Mr. Carpenter wanted the center line intersections monumented following a paving project. I recover monuments as shown. The McIn monuments at the intersection of Jackson Ave and Ash St. and the one at V Ave. and Ash St. were recovered prior to paving. I reset these at the tied positions. I place the intersection of Ash and X Avenues at proportionate position, as was done in Surveys 012-2013 and 006-2026. I find no unusual conditions with this survey.

UNION COUNTY SURVEYOR

Date Received 5/12/26

Date Filed 5/12/26

By [Signature]

File No. 019-2026

REGISTERED LAND SURVEYOR

[Signature]

OREGON JUNE 2, 2010

JEFFREY S. HSU 83571

Renewal Date: June 30, 2027.

BAGETT, GRIFFITH & BLACKMAN

2006 Adams Avenue, LaGrande, Oregon

Map of Survey

Intersection Monuments of North Ash St., from Jackson Ave. to Y Ave.

UNION COUNTY, OREGON

SURVEYED FOR Kyle Carpenter

SURVEYED BY J. S. H.

Scale: 1" = 50' Drawn by: K. A. T. Apr. 2026