



BASIS OF BEARING

Forward bearing as published by the U.S.C.
and G.S. from Δ COLLEGE to Δ VALLEY
Dated 1946.

SCALE: 1" = 20'

LEGEND

- Found 5/8" iron pin, set by Plat of Progress Plaza
- Found 5/8" iron pin, set by Plat of Minam View Addition
- ⊙ Found 5/8" iron pin, set by Plat of Minam View Addition, added 2" brass cap marked BAGETT GRIFFITH AND BLACKMAN in 4" collar of concrete at grade
- ⊕ Set cotton spindle reference
- Centerline

REFERENCE MATERIAL

Survey Number 030-2025
Partition Plat 20190015
Plat of Progress Plaza
Plat of Jordan East
Plat of Minam View Addition

NARRATIVE

This survey was done at the request of Kyle Carpenter, Public Works Director for the City of La Grande. Mr. Carpenter wanted the center line intersections monumented following a paving project. I recover said monument pre paving and find monument still in good condition post paving. I raise it to ground level and add a brass cap in collar of concrete. I show monuments in close proximity for reference and set two additional references. I find no unusual conditions with this survey.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Jeffrey S. Hsu

OREGON
JUNE 2, 2010
JEFFREY S. HSU
83571

Renewal Date: June 30, 2027

UNION COUNTY
SURVEYOR

Date Received *5/12/26*

Date Filed *5/12/26*

By *Jeffrey S. Hsu*

File No. 021-2026

BAGETT, GRIFFITH & BLACKMAN
2006 Adams Avenue, LaGrande, Oregon

Map of Survey
Centerline monument at intersection of
Minam Drive and 25th Street
City of La Grande

UNION COUNTY, OREGON

SURVEYED FOR	City of La Grande	
SURVEYED BY	J. S. H.	
Scale: 1" = 20'	Drawn by: K. A. T.	April 2026

SURVEY NUMBER 021-2026