

in T.5S R.40 E.10W. Surveyed for Hayes Lee Parcel & Titus May 2 1885

The 1/4 Sec corner on South Side Sec 9 thence west 20 chains set Post 4012 chains S.W. Corner Sec 9 from which I run East at 2006 chains set Post for 1/4 corner. The S.W. Corner Sec 9 thence North 20 chains set Post for 1/4 corner at 40 chains set Post for temporary 1/4 Sec corner 60 chains set Post for temporary 1/4 corner at 8027 chains the N.W. Corner Sec 9 from which I run South 2007 chains set Post for 1/4 corner 4014 chains Planted Stone marked 1/4 S or west face for 1/4 Sec. corners between Sec 8 & 9 at 6020 chains set Stake for 1/4 corner. thence I run west 20 chains and drove Stake for center S.E. 1/4 Sec 8.

I commenced at 1/4 Sec. corner on west side Sec 9 thence I run East 20 chains set Stake at 40 chains set Post for center Sec 9 60 chains set Stake for 1/4 corner 8020 chains 1/4 Sec corner on East side Sec 9 from which I run West 2005 chains 1/4 corner 4010 chains center 6015 chains 1/4 corner.

I started at 1/4 Sec corner on North side Sec 9 thence I run South 20 chains set Post 3960 chains the center Sec 9. thence I run South 20 chains set Stake for 1/4 corner 3980 chains 1/4 Sec. corner on South side Sec 9 from which I run North 1990 chains set Post for 1/4 corner thence East 2006 chains set Post for center S.E. 1/4 Sec 9. The center S.W. 1/4 Sec 9 thence West 2007 chains set Post for center S.W. 1/4 Sec 9. The 1/4 corner on west side N.W. 1/4 Sec 9 thence East 20 chains set Post in mound of Stone for center N.W. 1/4 Sec 9.

thence East at 1993 chains the center N.W. 1/4 Sec 9 at 4005 chains set Post for center N.E. 1/4 Sec 9, May 2, 1885. I commenced at N.E. corner Sec 8 thence West 20 chains set Post at 4017 chains the 1/4 Sec corner from which I run East and at 2008 chains set Stake for 1/4 corner.

The 1/4 Sec corner on North side Sec 8 thence I run South 20 chains set Post 40 chains set Post at 8035 chains the 1/4 Sec corner on South side Sec 8 thence East - at 20 chains set Post at 4040 chains the S.E. corner Sec 8.

I started at 1/4 Sec corner on East side Sec 8 thence West 20 chains set Post 4000 chains set Post in mound of Stone for center Sec 8 from which I run East 2010 chains set Post for center S.E. 1/4 Sec 8.

The 1/4 Sec corner on South side Sec 5 at 40 chains set Post for temporary center at 8083 chains 1/4 Sec corner on North side Sec 5. from which I run East at 40 chains set Stake for temporary corner to Sec 4-5-32833. at 7940 1/4 Sec corner from which I run West on township line and at 3970 chains set Stone for corner to Sec. 4-5-32833.

The N.E. corner Sec 4 thence South at 40 chains set Post at 8075 chains the S.E. corner Sec 4 from which I run North and at 4015 chains established 1/4 Sec corner thence West at 20 chains set Stake for 1/4 corner at 40 chains set Stake for center Sec 4

7997 chains 1/4 Sec corner on West side Sec 4. I started at corner to Sec 4-5-32833 thence North 40 chains set Post for temporary 1/4 corner at 8027 chains corner to Sec 4-5-32833 from which I run South making a deficiency of 8 links at the U.S. field notes. Therefore I run South and at 2033 chains set Stone for 1/4 corner and at 3996 chains established 1/4 Sec corner on West face thence West 3990 chains center Sec 5.

J.W. Kimbrell Capt. Co. Surveyors

Surveyed for Bayard Leep's Profit-Haining & Morrison June 21 1885

By J.W. Kimbrell Capt. Co. Surveyors Plat. No. 37

1890	1890	2004	2004	2005	2004		
3994		2005	2004	2005	2004		
1824	1976	2015	2015	2010	2005		
3994		4012		2007	2009		
1727	2011	4022		1998	1967		
1618		2003					
	1877	2002		4023	2006		
		2002					
4014		2002					
1851	1851						

I commenced this survey by Re-establishing the corner to Sec 6-7-12 and the 1/4 Sec corner between Sec 12 & 7 & 12 on Range line between townships 45 & 46 S. & S. The bearing line to the Sec corner U.S. Survey, a cottonwood 5 or 6 diameter bears N 50° E 275 links distant being cut down the of which is still in place. I therefore reestablished by planting a Post in mound of earth 8 or 10 links from which a 3 inch dia. bears N 48° 45' E 102 links distant an a 5 inch dia. bears S 24° W 77 links distant from this corner I run South prec. 20° E at 40 chains set temporary stake for 1/4 Sec corner at 8036 chains the corner to Sec 7-12-12313 from which I run North 4018 chains set Stone marked for 1/4 Sec corner between Sec 7 & 12 8036 chains Sec. corner. thence North true 21° E 40 chains set Post 7983 chains the N.W. corner Sec 6 from which

Surveyed for England Joseph Proffit Haring of Morrison & S. L. ...
 I run South between Sec 1 & 6, $21^{\circ}45'E$ at 3991 Planted Stone for
 1/4 Sec corner between Sec 1 & 6 on Range line between Ranges 45 & 46, S. 8.
 1995 chains set fast for 1/4 corner 7982 chains the corner to Sec 1-12-687.
 The corner to Sec 6-7-1812 Thence East 1725 chains set fast for 1/4 corner
 3725 chains set fast for temporary 1/4 Sec corner 7770 chains the corner to Sec.
 5-6-788 frame which I run West and at 4032 set Post marked
 1/4 on west face for 1/4 Sec corner between Sec 6 & 7 from which an app
 12 inches diameter bears East 15 links distant, at 6033 chains set
 Post for 1/4 corner 7770 chains the corner to Sec 1-12-687.
 The 1/4 Sec corner on west side sec. 7 Thence East 1800 1/4 corner 3777 chain
 the center Sec 7 at 6780 chains set fast for 1/4 corner 7784 1/4 Sec corner on east
 side sec. 7. Thence South at 20 chains set stake for 1/4 corner 4008
 chains corner to sec 7-8-1887 from which I run North and at 2007
 chains established 1/4 corner 4008 chas 1/4 Sec corner East side Sec. 7.
 Thence North 4013 chains corner to 5-6-788 a Stone in Swamp.
 The S.W. corner Sec 7, Thence East 1900 chains set fast for temporary
 1/4 corner at 3802 chains 1/4 Sec. corner on South side Sec. 7 making a
 deficiency of 88 links U.S. Field Notes. I therefore run West at 1956
 chains set fast for 1/4 corner 3802 chas S.W. corner Sec. 7
 The 1/4 Sec corner on south side Sec 7 Thence North 20 chains set fast for
 temporary 1/4 corner 40 chains set fast for temporary center 8009 chains 1/4 Sec. corner
 North side sec 7 from which I run South 4004 chains center 6006 chas 1/4 Sec.
 8009 chas 1/4 Sec. corner on North side Sec 7. The 1/4 Sec. corner North side Sec 7 Thence
 North 20 chains set stake for temporary 1/4 corner 40 chains set stake for temp.
 center 60 chains set stake for temporary 1/4 corner 7923 chains intersect North
 boundary Sec. 6. 85 links East of 1/4 Sec corner from which I run
 South on same line 1918 chains set fast for 1/4 corner 3923 chains center
 Sec 6 5929 1/4 corner 7923 1/4 Sec. corner. The 1/4 Sec corner on west side
 Sec 6 Thence East 1825 chains 1/4 corner 3808 chains center Sec 6
 7838 chains 1/4 Sec corner on east side Sec 6 from which I run
 West and at 2015 chains set fast for 1/4 corner from which a Pine 20 inch
 diameter bears $N20^{\circ}E39$ links dist. 4030 chain center Sec 6. The N.W. corner Sec. 6
 Thence East 3930 chains 1/4 Sec corner on North side Sec 6 a Pine 5' diam from
 which a Pine tree 23 inch diameter bears $N47^{\circ}30'W$ 14 links distant Thence
 East 20 chains set stake for temporary 1/4 corner at 7905 chains a stone but
 the distance would nothing to move the corner west of same I run East
 20 chas North on set stake for 1/4 corner and at 7114 chains found 1/4 Sec
 corner. I therefore run West 2005 chains set fast for 1/4 corner from which
 a Birch 8 inch diameter bears $S7^{\circ}45'E$ 77 links distant 4009 chains
 re-established corner to Sec 5-6-31432 a Stone marks for corner from
 which a Pine 24 inches diameter bears $N9^{\circ}15'E$ 492 links distant.
 6013 chains set fast for 1/4 corner. The 1/4 Sec corner on west side Sec 5 Thence
 South 20 chains set fast 4015 chain South East corner 90 links west of corner from
 which I run North and at 2007 chains set fast for 1/4 corner from which a
 Cottonwood 12 inch diam bears $S43^{\circ}15'W$ 14 links dist. 4018 chas 1/4 Sec. corner
 The S.W. corner Sec 5 Thence East 20 chains set fast for 1/4 corner 3926 chain
 1/4 Sec corner a Pine tree, from which I run West 1998 chains set fast for 1/4
 corner from which I run North through center W 1/4 Sec 5-20 chains set fast for temp.
 1/4 corner 40 chains set fast for 1/4 corner at 60 chas set fast 7950 chains North boundary Sec 5
 The 1/4 Sec corner on west side Sec 5 Thence East Thence to center

Surveyed for England Joseph Proffit Haring of Morrison & S. L. ...
 Sec 5 40 chains set stake for temporary center 7971 chains 1/4 Sec. corner which I reestablished
 Planted a stone from which a Pine 30 inch dia bears $N57^{\circ}30'E$ 145 links distant
 from which I run West 3971 chains center Sec 5 at 5970 chains 1/4 corner from
 which a Cottonwood 8 inch dia, bears $S88^{\circ}10'W$ 253 links distant Thence
 South 2007 chains set fast in center $S87^{\circ}1/4$ Sec. 5 from which a Cottonwood
 4 inches dia bears $S28^{\circ}W$ 35 links distant. The 1/4 Sec corner on South
 side Sec. 5 Thence North 20 chains set fast for temporary 1/4 corner 40 chains
 intersect first Sec. center Sec 5 60 chains set fast for temporary 1/4 corner at 7858
 chains 1/4 Sec corner on North side Sec 5. from which I run South 1830
 chains set fast for 1/4 corner from which a Cottonwood 30 inch dia, bears $S40^{\circ}$
 71 links distant the S.W. corner Sec 5, Thence East 20 chains
 set fast for temporary 1/4 corner 4013 chains 1/4 Sec corner on South
 side Sec. 5. Thence West 2007 chains set fast for 1/4 corner
 from which I run North bears 20° 20 chains set fast for temporary 1/4 corner
 40 chains set fast for 1/4 corner 60 chains set fast for temporary 1/4 corner
 chains North boundary Sec 5. from which I run South setting
 stakes at proportional distances 2006 & 2005 chains to be finished
 some other time. J.W. Koinbrell Capt. & Surveyor

Surveyed for James Mc Nut & Joel Hewit June 30 1888

By J.W. Koinbrell Capt. Co. Surveyor Plat No. 38
 I commenced at corner to Sec 4-5-8-9 Thence
 West 20 chains set stake for temporary 1/4 corner 2937
 chains 1/4 Sec corner between Sec 5 & 8 from which I run
 East 1968 set fast on corner of same for 1/4 corner 3937
 chains corner to Sec 4-5-8-9 Thence North at 20
 chains set stake for 1/4 corner 40 chains set fast
 for temporary 1/4 Sec corner (being obliterated)
 7984 chains the North boundary Sec 4 485 4 links
 West of corner to Sec 4-5-3233 being out of place
 I reestablished the same as per U.S. Field Notes. The
 bearing tree 11 Pine 36 inch dia. bears $N35^{\circ}E54$ links
 distant stand in Mr. Ervin's garden cut down
 from which I run South 3948 chains find a
 Stone marker for 1/4 Sec corner between Sec 4-5-
 from which a Pine 30 inch dia bears $N57^{\circ}30'E$ 145 links distant
 5966 chains set fast for 1/4 corner 7994 chains center to Sec 4-5-8-9
 Thence East 20 chains set stake for 1/4 corner 40 chains set fast
 for temporary 1/4 Sec corner, the same Pine set 60 chains set
 fast for temporary 1/4 corner 8036 chains the corner to Sec 3-4-7810
 from which I run West 2089 set fast from which an app 6 inch bears $N32^{\circ}45'E$ 150 links
 an app 4 inch bears $S53^{\circ}30'W$ 181 links 4018 chains set fast 6027 chas set stake for 1/4 corner 8036 chas
 The 1/4 Sec corner on west side Sec 4 Thence East 20 chains set fast 40 chains set fast
 60 chains set fast 7968 chains 1/4 Sec corner on east side Sec 4 from which I run
 West 2005 set fast for 1/4 corner from which an app 5 inch bears $N70^{\circ}W$ 71 links an app 6 inch bears
 $S23^{\circ}E$ 137 links 4011 chains center a set from which an app 3 inch bears $N22^{\circ}W$ 17 links
 a Pine 30 inch bears $S77^{\circ}W$ 253 links 5984 1/4 corner a set 7968 chains the same
 The 1/4 Sec corner on North side Sec 4 Thence South 3925 chains center 20050
 chains 1/4 corner from which a Pine 36 inch bears $S63^{\circ}W$ 92 links 7985 ch 1/4 Sec corner
 1/4 corner on center Sec 4 Thence South 2011 chains 1/4 corner from which an app
 4 inch bears $N60^{\circ}W$ 142 links, 1/4 corner on South side Sec 5 Thence North 2006 chas
 set fast from which a Pine 20 inch bears $S25^{\circ}10'W$ 35 links Thence East 1977 chas 1/4 corner set fast, a

	1888	46.6000	
James Mc Nut	2009	2002	2002
Joel Hewit			2002
			A.B. Cary