

I commenced at the 1/4 Sec corner on the South Side of Sec 26
 Thence I run North var. 19° 45' E 8135 chains the 1/4 Sec corner on
 the North Side Sec 26 from which a Pine 14 inch dia. Bears N 50° W 37 links
 a Pine 20 inch Bears S 52° W 50 links distant from which I run South
 2022 chains set post for 1/16 corner from which a Pine 20 inch Bears N 35° 45' E
 81 links dist. a Pine 20 inches Bears S 85° 35' E 98 links dist.
 4044 chains set post for center 26 from which a Pine 18 inches
 Bears N 42° 45' E 49 links distant a Pine 18 inches Bears S 40° W 81 links
 6080 chains set post for 1/4 corner from which a Pine 24 inch
 dia. Bears N 29° E 13 links dist. a Pine 10 inches Bears S 55° W 77 links
 I started at 1/4 Sec corner on West Side of Sec 26 from which
 a Sawrack 14 inches Bears S 9° E 73 lbs a Sawrack 18 inches
 Bears S 1° W 46 lbs distant. Thence East through the center
 Sec 26 4058 chains the center Sec 26 8123 chains the 1/4 Sec
 corner on East Side Sec 26 from which a Pine 23 inch
 Bears S 65° W 90 links a Pine 7 inches Bears N 88° E 31 lbs.
 from which I run West 2033 chains and set post for
 1/16 corner from which a Pine 20 inch Bears S 78° 30' W 148
 links dist. a Pine 15 inch Bears N 57° E 152 links distant
 the 1/4 Sec corner on East Side Sec 26 Thence North 4080 chains the
 corner to Sec 23 = 24 = 25 & 26 from which I run South 2040 chains set
 post for 1/8 corner in mound of Stone from which a Pine 24 inch
 Bears S 55° 30' E 4 links dist. a Pine 14 inch Bears N 1° W 23 links distant.
 Thence West 4061 chains 1/16 corner in center of Sec 26 from
 which I run East 2031 chains set post for 1/8 corner in center of Sec 26
 from which a Pine 10 inch Bears S 46° E 230 links distant a Pine
 14 inches Bears N 42° W 150 links distant
 the 1/4 Sec corner between Sec 25 & 26 Thence East through the center
 Sec 25 7991 the 1/4 Sec corner on East Side Sec 25 from which a Pine
 24 inch Bears N 40° W 29 links dist. a Pine 20 inch Bears N 52° E 53 links
 Thence North 4072 chains the corner to Sec 24 = 25 = 26 from which
 a Pine 34 inches dia. Bears S 74° W 68 links distant
 a " 32 " " " " " S 12° E 106 " " "
 a " 33 " " " " " N 41° W 29 " " "
 a " 22 " " " " " N 51° E 80 " " "

Thence West var 21° E 3926 chains the 1/4 Sec corner between Sec 24 & 25
 from which a Pine 28 inches dia. Bears S 83° W 276 links distant
 a Pine 34 inches Bears N 73° W 239 links distant from which I run
 East 1963 chains set post for 1/8 corner Thence South 2035 chains
 set post for mound of Stone for 1/16 corner in center N. E. 1/4 Sec 25 -
 the 1/4 Sec corner on North Side Sec 26 Thence South 2033 chains set
 post in mound of Stone for 1/8 corner in center of N. E. 1/4 Sec 25 4067
 chains the center Sec 25 at 8157 chains the 1/4 Sec corner on South
 Side Sec 25 from which a Pine 15 inch Bears N 55° W 67 links dist.
 a Pine 22 inch Bears S 36° E 26 links distant Thence North
 4090 chains the center Sec 25 Thence West 2004 chains set post in
 mound of Stone for 1/8 corner in center W. E. 1/4 Sec 25. The North boundary N. E. 1/4 Sec 25
 4054 chains

The 1/4 Sec corner on South Side Sec 24 Thence North through center Sec 24
 8270 chains to 1/4 Sec corner on North Side Sec 24 from which a Pine
 12 inches Bears N 23° W 23 links a Pine 24 inches Bears S 19° E 98 links
 Thence East 4062 chains the corner to Sec 18 = 19 = 13 & 24
 from which I run West 2031 chains set post in mound of Stone
 from which I commenced at 1/4 Sec corner on West Side
 Sec 24 from which a Pine 26 inches dia Bears S 47° E 222 links dist
 Thence East through center Sec 24 var 20° E 20 chains set post for
 temporary 1/8 corner 4031 chains intersect N. E. S. line 84 links North
 of first stake to center 600 chains set stake for 1/8 corner 8108 chains
 intersect East boundary Sec 24. 464 links South of
 1/4 Sec corner from which a Pine 14 inch Bears N 71° 30' E 88 links
 a Pine 18 inch Bears West 36 links distant from which
 I run West on true line S 88° 20' W on true line var 20° E
 2039 chains set post from which a Pine 34 inch Bears N 43° E
 153 links dist. Thence West 2039 chains set post for center Sec 24
 from which a Pine 6 inch Bears S 37° W 23 links a Pine
 4 inches Bears N 67° 30' W 31 links dist. a Pine 10 inch Bears
 N 75° E 80 links dist. Thence West 2016 chains set post for
 center W. E. Sec 24 from which a Pine 14 inch Bears
 N 59° E 79 links dist. a Pine 18 inch Bears S 79° W 126 links dist.
 From the center Sec 24 I run South 2153 chains set post
 for center of 3/4 Sec 24 The 1/4 Sec corner on
 East Side Sec 24 Thence South var 20° E 4388 chains
 the South boundary Sec 19 & 24 300 links East of corner
 of Sec 19 = 20 = 24 & 25 from which I run N. 4°
 East 2196 chains set post for 1/8 corner from which
 a Pine 20 inches Bears N 56° W 49 links a Pine 30 inches
 Bears S 48° W 51 links 4388 chains the 1/4 Sec corner between
 Sec 24 & 19 Thence North 3911 chains the corner to Sec
 18 = 19 = 24 & 13 from which I run South var 20° E
 1955 chains set post for 1/8 corner from which a Pine 6 inch
 Bears S 5° E 212 links dist. a Pine 14 inch Bears S 87° W
 168 links distant. The 1/8 corner on East Side S. E. 1/4 Sec
 24 Thence West 20 chains set post for center S. E. 1/4 Sec 24
 from which a Pine 14 inches Bears N 62° W 136 links dist.
 a Pine 12 inch Bears S 54° 30' E 81 links distant Thence
 West 40 chas 1/16 corner in center S. E. 1/4 Sec 24

J. W. Kimbrell County Surveyor

