

4077 The 1/16 corner in cut Sec 5 as described above on S 1/4 W line
a Post from which
a Pine 3 ins dia to S 61° 8 1/2 lks dist-

6050 set Post for 1/16 corner for cut S 1/2 Sec 5
from which I mark
a Pine 3 ins dia to N 65° W 17 lks dist-

8022 The 1/4 Sec corner to Sec 5 & 8
I commenced at the 1/4 Sec corner to Sec 5 & 6
thence South to Sec 5 & 8
Var 20° E

2000 set temporary 1/16 corner
3978 Intersect 78 lks East of the corner to Sec 5-6-7 & 8
from which
a Sawrash 12 ins dia to S 48° 8 25 lks dist-
" 12 " " " S 22° W 6 " "
" 14 " " " N 63° W 48 " "
a Pine 12 " " " N 40° S 60 " "
thence North 107' E on true line

1989 set Post for 1/16 corner
7978 The 1/4 Sec corner to Sec 5 & 6
I commenced at the corner to Sec 1-6-7 & 12
on Guide Meridian to S 18 N 16 39 40 E
from which
a Pine 30 ins dia to S 20° S 274 lks dist-
a " 40 " " " S 42° W 427 " "
Var 1° E
thence North to Sec 1 & 6
Var 21° 15' E

2000 set temporary 1/16 corner
4030 Intersect 38 lks West of the 1/4 Sec corner to Sec 1 & 6
from which
a Pine 30 ins dia to N 87° W 149 lks dist-
" 20 " " " S 25° W 127 " "
So 33' W on true line

2016 set Post for 1/16 corner
4030 The corner to Sec 6-7-1 & 12

I commenced at the corner to Sec 5-6-7 & 8
thence South to Sec 7 & 8 on random line
Var 20° E

2000 set temporary 1/16 corner
4050 I intersect 166 lks West of the 1/4 Sec corner to Sec 7 & 8
thence True N 2° 22' W on true line

2025 set Post for 1/16 corner
4050 The corner to Sec 5-6-7 & 8
I then commenced at the 1/4 Sec corner to Sec 7 & 8
and ran South to Sec 7 & 8
Var 29° E

700 Var 28° 30' E
1200 Road S & W
1591 Top of cliff S & W
3911 Intersect 170 lks West of the corner to Sec 7-8-17 & 18
thence True N 2° 40' W on true line

1955 set Stone for 1/16 corner in end of Stone
3911 The 1/4 Sec corner to Sec 7 & 8
J.W. Trimball
County Surveyor

Sworn for Wm B. Brothie June 25th 1890
by J.W. Trimball County Surveyor Plat No 116

I commenced at the corner to Sec 5
20-21-28 & 29 which is a Stone corner.
reset by myself as county Surveyor on
March the 29 1889 see Page 81 this book
thence True East to Sec 21 & 28
on random line Var 20° 15' E

Sec 20	Sec 21
Sec 29	Sec 28

1850 Spring branch runs S.W.
2000 set temporary 1/16 corner
4000 found low 1/4 Sec corner at Spring 1/2, Exposed East
8068 Intersect 18 lks South of the corner to Sec 21-22-27 & 28
thence True S 89° 52' W on true line

4034 set Post in Stone mound for 1/4 Sec corner to Sec 21 & 28
6051 set Post for 1/16 corner
8068 The corner to Sec 20-21-28 & 29
J.W. Trimball County Surveyor