Stryker-Kimbell Associates Pte. 1 Box 316 Lewis Creek Road Summerville, Oregon 97876 503-534-6905 12 August, 1989

Office of County Surveyor Union County
LaCrande, Oregon

NARRATIVE per USDA FS Contract .00-04R3-9-1 JEMINA CADASTRAL SURVEY

This survey was performed at the request of the USDA Forest Service, the Umatilla National Forest, headquartered in Pendleton, Oregon.

This survey was performed within Township 4 North, Pange 39 East. W.M. as a subdivision of Section 13 to monument and establish the ownership and the boundaries of the public lands within said section, Union County, Oregon.

The basis of bearing was a solar observation taken from the northeast section corner monument of said section 13, on 31 May )]989.

The survey was performed using a Wild TI micrometer theodolite and a Wild DI-4L electronic distance meter turned to Wild targets and prisms. A chosed random traverse was used to tie all controlling monuments within said section meeting precision standards of one in ten thousand prior to angle balance. A least squares adjustment procedure was used. True line closed loop traverses were performed to establish property lines, and offset methods were used to set steel fence posts along the true property lines. These also met the same precision standards noted above.

Two lost corners could not be recovered during this survey; the N1/4 corner common to sections 12 and 13, and the S1/4 corner common to sections 13 and 24. After extensive search failed to recover these CLO corners, they were set using single proportionate measure from found and tied controlling section corners to the east and west of both positions. The NW section corner, the W1/4 corner, and the SW section corner all of said section 13 were recovered from found original accessories. They were re-established based on distance and bearing information from GLO notes using compass and chaim.

When posting the property boundaries, timber cutting encroachment was apparent along the north line, the east line, and the south line of the SF one-quarter of the section. The cutting lines were blazed and are well healed; the encroachments are not new, and generally are less than 20 feet.

UNION COUNTY SURVEYOR

Date Received 10-2-89

Day 5:1-1 10-11-80

Date Filed 10-11-89

NAPRATIVE DRAG

REFER TO SURVEY 24-89

Cortified

Edwin A. Stryke

Oregon PLS 2060