

NARRATIVE TO ACCOMPANY BAKER COUNTY SURVEYS
 NOS. 6-39-1 and 6-39-2

This part of narrative describes corner monumentation found and/or established during the course of Farmers Home Administration Survey in Sections 23, 24, 25 and 26, T. 6 S., R. 39 E., W.M. under the above filing numbers.

The original monumentation was established by use of wood posts, set in mounds of earth. This survey has accepted the fence corners at these locations as having perpetuated the locations as originally established. Except as indicated otherwise, the only existing remains of these posts were found at the corner common to Sections 23, 24, 25 and 26, and at the quarter corner between Sections 23 and 24. Marked stones were found along the East line of the township (Guide Meridian) for the Southeast and Northeast corners of Section 25 and the quarter corner between Sections 23 and 24, and were accepted as replacements for the original wood posts, although no documentation was found for the monumentation.

T. Davenport surveyed the East Range line of T. 6 S., R. 39 E. under GLO Contract No. 102, approved 1/12/1864.

D. Thompson surveyed the interior of this township under GLO Contract No. 103, approved 1/20/1864.

N-17 Corner common to Sections 14, 15, 22 and 23: GLO records state "set post for corner to Sections 14, 15, 22 and 23". Found a 3/4-inch diam. pipe in 3-way fence intersection. Point not remonumented.

N-19 Quarter corner between Sections 14 and 23: GLO records state "set post for corner in mound of earth". Found a 3-way fence intersection. Set 5/8-inch x 30 inch rebar with plastic cap mkd. HANLEY ENGRG PLS 1206 at cor point.

N-21 Corner common to Sections 13, 14, 23 and 24: GLO records state: "set post for corner to Secs. 13, 14, 23 and 24 in mound of earth". Found 2-way fence corner. Set 5/8-inch x 30 inch rebar with plastic cap mkd. HANLEY ENGRG PLS 1206 at corner point.

N-23 Quarter corner between Sections 13 and 24: GLO records state "set post for corner...in mound of earth". Found 4-way fence corner. Set 5/8-inch x 30 inch rebar with plastic cap mkd. HANLEY ENGRG PLS 1206.

P-17 Quarter corner between Sections 22 and 23: GLO record states "set post for corner ...in mound of earth"... Extended the North and East running fence lines South and West to intersection point. Set 5/8-inch x 30 inch rebar with plastic cap mkd. HANLEY ENGRG PLS 1206.

P-21 Quarter corner between Sections 23 and 24: GLO record states "set post for corner in mound of earth...". Found remains of rotted post in center of 5 stone mound located in North-South running fence line. Set 2½-inch brass cap on 1½-inch iron pipe projecting 4 inches above ground with 24-inch stone mound around monument. Set fence post

T 6 S R 39 E

one foot West of monument.

Monument mkd. thus: $\frac{1}{4}$

S 23		S 24
CS 1989		

R-17 Corner common to Sections 22, 23, 26 and 27: GLO records state "set post for corner to Sections 22, 23, 26 and 27 in mound of earth...". Found 4-way fence intersection. Point not monumented this survey.

R-19 Quarter corner common to Sections 23 and 26: GLO records state "set post for corner in mound of earth". Found fence corner, fence runs North, West and Southeasterly. Set 5/8-inch x 30 inch rebar with plastic cap mkd. HANLEY ENGRG PLS 1206.

R-21 Corner common to Sections 23, 24, 25 and 26: GLO records state "set post for corner to Sections 23, 24, 25 and 26 in mound of earth with charred stake..". Found charcoal remains one foot under surface in center of 3 stone mound (large stones) in ancient fenceline remains. Set 2½-inch brass cap on 1½-inch diam. iron pipe projecting 2 inches above ground with 36 inch diam. stone mound around the monument. Set fence post alongside.

T 6 S R 39 E

Monument mkd. thus: $\frac{1}{4}$

S 23		S 24
S 26		S 25
CS 1989		

R-23 Quarter corner between Sections 24 and 25: GLO records state: "set post for corner in mound of earth...". Set a 5/8-inch x 30 inch rebar with plastic cap mkd. HANLEY ENGR PLS 1206 in North-South running fence line on line between Southeast and Southwest section corners.

R-25 Corner common to Sections 19, 24, 25 and 30: GLO records state "set post corner to Sections 19, 30, 24 and 25, made mound of earth"... Found a 15 x 11 x 9 inches stone in rock jack mkd. with 6 grooves on each of two sides and 2 grooves on one other side. Accepted rock jack for corner position. Did not remonument.

T-17 Quarter corner between Sections 26 and 27: GLO records state "set post for corner in mound of earth...". Set 2½-inch brass cap on 1½-inch iron pipe, 30 inches long in 36 inch diam. mound, in North-South running fence line at proportionate distance between Northwest and Southwest section corners.

T 6 S R 39 E

Monument mkd. thus: $\frac{1}{4}$

S 27		S 26
CS 1989		

- T-21 Quarter corner between Sections 25 and 26: GLO records state "set post for corner in mound of earth..". Set 5/8 inch x 30 inch rebar with plastic cap mkd. HANLEY ENGRG PLS 1206 in center of Baker County road on projected line of North-South running fence. Road has obliterated corner point. Road records indicate centerline and mid-section line are coincident.

- T-25 Quarter corner between Sections 25 and 30: GLO records state "set post in mound of rock". Found fence corner at this location, did not remonument this survey.

- V-17 Corner common to Sections 26, 27, 34 and 35: GLO records state "set post for corner to Sections 26, 27, 34 and 35 in mound of earth ...". Found a 3-way fence intersection. Fences run North, East and West. Point not remonumented this survey.

- V-19 Quarter corner between Sections 26 and 35: GLO records state "set post for corner in mound of earth..". Found 4-way fence intersection, did not remonument this survey.

- V-21 Corner common to Sections 25, 26, 35 and 36: GLO records state "set post for corner to Sections 25, 26, 35 and 36 in mound of earth...". Found 3-way fence intersection of fences running North, East and West, did not remonument this survey.

- V-23 Quarter corner common to Sections 25 and 36: GLO records state "set post for corner in mound of earth..". No evidence found. Point was established by single proportionate method between Southeast and Southwest section corners. Did not remonument this survey.

- V-25 Corner common to Sections 25, 30, 31 and 36: GLO records state "set post for corner to Sections 30, 31, 25 and 36". Found a 13 x 9 x 6 inches stone firmly set in ground at 3-way fence intersection with 5 grooves on North face and one groove on South face. Did not remonument this survey.

WAGON COUNTY SURVEYOR	
Received	<u>12/18/91</u>
Filed	<u>12/20/91</u>
By	<u>Greg Black</u> Narrative Drawer
File No.	<u>1/18</u>

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

James D. Hanley

OREGON
SEPTEMBER 22, 1977
JAMES D. HANLEY
1206

HANLEY ENGINEERING
2043 MAIN STREET
BAKER, OREGON