RESTORED:

Set 5/8" x 30" iron pin 24" in ground. Set 4" x 4" x 48" white post near pin scribed, "T2S R36E S36 E $\frac{1}{4}$ COR" 13" Pine N84 $\frac{1}{2}$ °E 27.5 ft. scribed, "T2SR37ES31BTRS691" Yellow corner tag on original BT.

Witnessed by: A. Slack

R. Hemmer

T. Stose

E - E - 1/64

ESTABLISHED:

Set 5/8" x 30" iron pin Set 4" x 4" x 48" white post near pin.

Witnessed by: E. Haury

D. Shaw

T. Stose

SE - SE - 1/64

ESTABLISHED:

Set 5/8" x 30" iron pin Set 4" x 4" x 48" white post 10" Pine S402°W 45.6 ft. scribed, "SESE 1/64 BTRS691"

Witnessed by: E. Haury

D. Shaw

T. Stose

C - N - SE - SE 1/256

ESTABLISHED:

Set 5/8" x 30" iron pin.
Set 4" x 4" x 48" white post near pin.
10" Pine S42°W 67.6 ft. scribed, "CNSESE 1/256 BTRS691"

Witnessed by: E. Haury

D. Shaw

T. Stose

WITNESS CORNER (304.59 ft. S89°27'E of C-N-SE-SSE 1/256)

ESTABLISHED:

Set $5/8" \times 30"$ iron pin near bank of Grande Ronde River Set $4" \times 4" \times 48"$ white post near pin. Erected mound of stone around pin.

Witnessed by: E. Haury

D. Shaw

T. Stose

Constitution Constitution of C	UNION COUNTY SURVEYOR	
on part to have been designed to the second	Date Received	
	Date Filed By NARRATIVE DRAWER 1/3	
	File No.	and and an article

REPORTO SURVEY 6-82

WITNESS CORNER (230.00 ft. NO° $37\frac{1}{2}$ 'E of S-S 1/64 between sections 36 and 31) ESTABLISHED:

Set $5/8" \times 30"$ iron pin on gravel bar on the South side of the Grande Ronde River.

Set 3" x 84" iron post and paddle marked, "OREGON STATE PARK BOUNDARY do not disturb". Erected mound of stone around pin.

Witnessed by: E. Haury

D. Shaw

T. Stose

S-S 1/64 BETWEEN 36 and 31

ESTABLISHED:

Set 5/8" x 30" iron pin. Set 4" x 4" x 48" white post near pin.

Witnessed by: E. Haury

D. Shaw

T. Stose

REGISTERED OREGON LAND SURVEYOR

JULY 9, 1965

John E. Hollingsworth

691

UNION COUNTY SURVEYOR
Date Received
Date Filed
NARRATIVE DRAWER 1/3 File No.
File No.

REFER TO SURVEY 6-82