

The 1/4 Sec corner bet Sec 35 & 36
Thence S 89° 45' E

20 45 Set Post in Mound of Stone for 1/6 corner in center w 1/2 Sec 36
40 90 from which
a Pine 20 inches dia. bcs N 40° 30' W 90 lks dist.
" 3 " " " S 16° 45' E 42 " "

40 90 The center Sec 36

61 01 Set Post for 1/6 corner in center E 1/2 Sec 36 from which
a Pine 20 inches dia. bcs S 81° 30' E 19 lks dist.
" " " " S 85° W 75 " "

81 12 The 1/4 Sec corner bet Sec 31 & 36

The corner to Sec 25 = 36 = 30 & 31
Thence West bet Sec 25 & 36 var 20° E
ascend very steep Mountain Side Slopes to the N E

20 00 Set temporary 1/8 corner

40 06 The 1/4 Sec corner bet Sec 25 & 36
Thence East on line

20 03 Set Post in Mound of Stone for 1/8 corner from which
a Pine 14 inches dia. bcs S 41° W 110 lks dist.
" 13 " " " N 81° W 77 " "

40 06 The corner to Sec 25 = 36 = 30 & 31

The 1/8 corner on North Boundary N E 1/4 Sec 36
Thence South var 20° E

20 00 Set temporary 1/6 corner

41 04 The 1/6 corner in center E 1/2 Sec 36 from which
Thence North var 20° E

20 52 Set Post in Mound of Stone from which
a Pine 8 inches dia. bcs N 18 1/4° W 44 lks dist.
" 7 " " " N 3 1/4° E 29 " "

The 1/4 Sec corner bet Sec 1 & 36
Thence East bet Sec 1 & 36

20 00 Set temporary 1/8 corner

40 77 The corner to Sec 1 = 6 = 31 & 31 from which Thence West

20 38 1/2 Set Stake for 1/8 corner from which
a Pine 8 inches diameter bcs S 61° 45' E 45 lks dist.
" 7 " " " N 9° 45' W 25 " "
Thence North var 20° E through center E 1/2

20 07 Set Stake for 1/6 corner in center S 8 1/4 Sec 36 from which
a Pine 9 inches diameter bcs S 14° E 100 lks dist.
" 7 " " " N 49 3/4° E 26 " "

40 14 The center E 1/2 Sec 36