

Township

Range

Union County, Oregon.

Thence North between Sec 5 & 6
Var 20° E

4000 found No 1/4 Sec corner but at
4072 the 1/4 Sec corner bet Sec 5 & 6 a Post in Mound of Stone
making an Excess of 72 lks over U.S. Field Notes
In the 1 1/2 miles retraced

I therefore ran South allowing 24 links to each
1/2 mile and at

4024 I re-established the corner to Sec 5-6-7 & 8
by setting a Post 4 inches Square 3 1/2 feet long 18 inches
in the ground with a Handfull of Charcoal at the
bottom of Post Built mound of Earth dug pits
S & S.W. N.E. & N.W. from Post 5 feet distant
Thence South Var. 20° E

2012 Set Post 4 inches Square and 3 1/2 feet long 18 inches in
the ground with a handfull of Charcoal at bottom
of Post Built mound of Earth with pits E. & W. 5 feet from Post

4024 Set Post 4 inches Square 3 1/2 feet long 18 inches in the
ground with handfull of Charcoal at bottom of
Post with Mound of Earth with pits E & W 5 feet from Post

8048 The corner to Sec 7-8-17 & 18

Thomas Shaw Chairman
J. C. Childers "

J. W. Kimbrell Deputy Co. Surveyor