

RECORD OF SURVEY

27

1887

Township 3 South Range 38 East N. M. Union County, Oregon.

The $\frac{1}{4}$ Sec corner between Sec 33 & 34

Hence East through Sec 34 Mar 20 E.

2000 Set temporary $\frac{1}{16}$ corner

4014 Intersect N & S line at center

Hence West

2007 Set Post in mound of Stone for Center W $\frac{1}{2}$ Sec 34

4014 The $\frac{1}{16}$ Sec corner set Sec 33 & 34

The $\frac{1}{16}$ corner in center W $\frac{1}{2}$ Sec 34

Hence North Mar 20 E

2000 Set temporary center N.W. $\frac{1}{4}$

4018 Intersect North Boundary at $\frac{1}{8}$ corner

Hence South

2009 Set Post and Built mound for $\frac{1}{16}$ corner for center N.W. $\frac{1}{4}$

4018 The $\frac{1}{16}$ corner in center N.W. $\frac{1}{4}$ Sec 34

The center Sec 34

Hence North Mar 20 E

2011 Set Post in mound of Stone for center N $\frac{1}{2}$ Sec 34

4023 The $\frac{1}{16}$ Sec corner set Sec 27 & 34

The center Sec 34

Hence East Mar 20 E

2000 Set Post for center E $\frac{1}{2}$ Sec 34

Hence North Mar 20 E

2000 Set temporary $\frac{1}{16}$ corner in center N $\frac{3}{4}$ Sec 34

4023 The $\frac{1}{16}$ corner on N Bay N $\frac{3}{4}$

from which run South

2011/2 Set Post in Md of Stone

4023 The center E $\frac{1}{2}$ Sec 34

J.W. Kirrell Asst Co Surveyor