

CHAINS
LKS.

P. H. Miles was Miles Saw Emilio & J M Sean. Claud Bowman Apr. 12 / 1888 -

I Commenced at the corner to
Sec 1-2-35 & 36 on Tpline
bet T. 7, 8, S. R. 41, E.

Thence west on Tpline
bet Sec 2 & 35 var 20° E

2000 Set temporary 1/8 corner
4000 found no 1/4 Sec corner and set
temporary 1/4 Sec cor
4125 Powder River 166 lks across
course of river S 25° E

6000 Set temporary 1/8 cor.
8000 found no Sec cor and
Set temporary cor.

Thence west var 20° E
3850 The 1/4 Sec corner bet Sec 3 & 34
making a deficiency of 150
lks in the whole distance as
Per U S Field notes.

The falling therefore would
be 25 lks to each 1/4 mile and
50 lks to each 1/2 mile East

Thence East on Tpline

3950 Set Stone built mound of Earth &c
for corner to Sec 2-3-34 & 35 -
Thence East on Tpline

1975 Set Stone in willow brush for corner

3950 Set Stone 6 + 8 + 10 inch for 1/4 Sec corner to Sec 2 & 35 -

5425 Set Stone 6 + 9 + 15 for 1/8 corner

7900 The corner to Sec 1-2-35 & 36

Thence North bet Sec 35 & 36 var 20° E

2000 Set temporary 1/8 corner

4000 found no corner Set temporary 1/4 Sec

6000 Set temporary 1/8 cor

8000 found no Sec corner

Thence North

4000 The 1/4 Sec corner bet Sec 25 & 26 a Stone in bud of Stone

The corner to Sec 2-3-34 & 35 -

Thence North var 20° E

2000 Set temporary 1/8 corner

3150 Powder River course S 85° E 186 lks across

