

RECORD OF SURVEY

Township 4 South

Range 40 & 41 East

Union County, Oregon.

CHAINS. LKS.

The 1/4 Sec corner bet Sec 30 & 31

Thence South through Sec 31 S 5° E var 20° E

40 00 Set temporary center Sec 31

80 00 Intersect E & W line 110 lks west of 1/4 Sec corner

Thence N 5° 1' W on true line

40 00 Set Post for center Sec 31

80 00 The 1/4 Sec corner bet Sec 30 & 31

The 1/4 Sec corner bet Sec 25 & 30 on Range line

Thence West through Sec 25 - var 20° E

40 00 Set temporary center Sec 25 -

60 00 Set temporary 1/16 corner. West of this point is inaccessible on account of High Cliff of Rock

The 1/4 Sec cor bet Sec 25 & 36

Thence North through Sec 25 - var 20° E

41 53 Intersect E & W line 20 lks East of 1st Temporary Stake

61 53 Set temporary 1/16 cor

81 53 Intersect E & W line but found no 1/4 Sec corner

I therefore proceeded to the corner to Sec 19 = 30 = 24 & 25 -

on Range line a stone in mound of Stone

Thence West bet Sec 24 & 25 - var 20° E

39 71 Set temporary 1/4 Sec Post

79 42 found no Sec corner Set temporary Post

Thence West

40 10 found no 1/4 Sec cor

40 66 The 1/4 Sec corner bet Sec 23 & 26 a Stone in mound of Stone

Thence East

40 23 Set Stone 6 x 12 x 24 for corner to Sec 23 = 24 = 25 & 26

Thence East

39 84 Set Stone 6 x 10 x 20 in for 1/4 Sec corner

79 68 The corner to Sec 24 = 25 = 19 & 30

The corner to Sec 23 = 24 = 25 & 26 Thence South var 20° E

39 93 The 1/4 Sec corner bet Sec 25 & 26 a Stone in mound of Stone

Thence North

19 97 Set Stone in mound of Stone ^{to lks W} Thence East

20 00 Set Stone for 1/16 corner Thence South

19 96 Set Stone for 1/16 cor in center N. W. 1/4 Sec 25 -

J. W. Kempf Deputy