

CHAINS	LKS.	
		The 1/4 Sec corner bet Sec 35 & 36 Thence North
43	14	The corner to Sec 25-26-35 & 36 Thence West var 20° E
41	00	The 1/4 Sec corner bet Sec 26 & 35 -
61	00	Set temporary 1/8 cor
93	85	Intersect N & S line 625 lks North of corner to Sec 26-27-34 & 35 - Thence N 82° 04' E on true line
26	42 1/2	Set Stone for 1/8 corner
52	85	The 1/4 Sec cor Thence South through Sec 35 - var 20° 15' E
20	00	Set temporary 1/6 corner
40	00	Set temporary center Sec 35 -
60	00	Set temporary 1/6 cor
86	20	The 1/4 Sec corner on South Boundary Sec 35 - Thence North
21	12	Set Stone in mound of Stone for 1/6 cor in Center S 1/2 Sec 35 -
42	25	Set Stone in mound of Stone for Center Sec 35 -
64	33	Set Stake in mound of Stone for 1/6 cor in Center N 1/2 Sec 35 -
86	20	The 1/4 Sec corner bet Sec 26 & 35 - The 1/4 Sec cor bet Sec 34 & 35 - Thence East through Sec 35 - var 18° E
20	00	Set temporary 1/6 cor
52	60	The center Sec 35 - Thence west -
26	30	Set Stone in mound of Stone for 1/6 cor in W 1/2 Sec 35 - Thence South
20	62	Set Stone in mound of Stone for center S W 1/4 Sec 35 -
41	25	The 1/8 corner on South Boundary Sec 35 - The corner to Sec 25-26-35 & 36 Thence North var 20° E
20	00	Set temporary Post for 1/8 cor
40	50	The 1/4 Sec corner bet Sec 25 & 26 Thence West through Sec 26 var 20° E
40	00	Set temporary Center Sec 26
92	87	Intersect N & S line 488 links North of 1/4 Sec cor bet Sec 25 & 26 Thence N 86° 30' E on true line
54	67	The center
92	87	The 1/4 Sec cor The 1/4 Sec corner bet Sec 26 & 35 - Thence North through Sec 26