

188. which is also the corner to 17 1/2 S Range 45 1/2 46 East Stone in mound of Stone

Thence S 1° 37' East on line

34 92 Set Post in mound of Stone for 1/4 sec on bet Sec 1 & 6

54 81 Set Post for 1/8 corner

79 82 The corner to Sec 6=7=18/12

Thence East (var 20° E

17 25 Set temporary 1/8 corner

37 25 found old 1/4 sec corner

77 70 The corner to Sec 5=6=7 & 8

Thence West on line

40 25 1/2 Set Post for 1/4 sec corner bet Sec 6 & 7

from which

in a 12 inch dia. lead East 15 links dist

69 58 Set Post for 1/8 corner

11 80 The corner to Sec 6=7=18/12

The 1/4 sec corner bet Sec 7 & 12

18 00 Set temporary 1/16 corner

37 77 Set temporary onto Sec 7

57 80 Set temporary 1/16 corner

71 84 The 1/4 sec corner bet Sec 7 & 8

Thence South (var 20° E

20 50 Set temporary 1/8 corner

40 08 The corner to Sec 7=8=17 & 18

Thence North

20 34 Set Post for 1/8 corner

40 08 The 1/4 sec corner bet Sec 7 & 8

Thence North (var 20° E

40 18 The corner to Sec 5=6=7 & 8 - Stone in mound of Stone

The corner to Sec 7=18=12 & 13

Thence East

19 50 Set temporary 1/8 corner

38 02 Set Post 26 links South of 1/4 sec corner bet Sec 7 & 18 -

Making a deficiency of 88 links as per US field notes

Thence S 89° 39' W on line

19 50 Set Post for 1/8 corner

38 02 The corner to Sec 7=18=12 & 13

The 1/4 sec corner bet Sec 7 & 18

Thence North (var 20° E

20 00 Set temporary 1/16 corner