

- but the distance being deficient and no good evidence as to the originality of the corner. I therefore extend my line East and find the distance between this point and the 1/4 sec corner bet Sec 5 & 32 to be 4114 chains. I therefore establish the corners on this line as follows
- The 1/4 Sec corner bet Sec 5 & 32  
 Thence West on Meridian
- 20 05 Set Post for 1/8 corner from which  
 a Birch 8 inch dia bears S 7 1/4° E 77 links distant
- 40 19 Set Stone 6 x 8 x 20 inches for corner to Sec 5-6-31 & 32  
 from which  
 a Pine 24 inch dia. bears N 9 1/4° E 492 links distant  
 Thence West
- 20 05 Set Post for 1/8 corner  
 40 9 The 1/4 Sec corner bet Sec 6 & 31  
 The 1/4 Sec corner bet Sec 5 & 6 a Pine 10 inches  
 Thence South 1/2 mile
- 40 15 The corner to Sec 5-6-71 & 8  
 Thence North on line
- 20 07 1/2 Set Post for 1/8 corner from which  
 a Cottonwood 12 inches dia bears S 43 1/4° W 14 links distant
- 40 15 The 1/4 Sec corner bet Sec 5 & 6  
 The corner to Sec 5-6-78 & 8  
 Thence East
- 20 00 Set Temporary 1/8 corner  
 39 96 Set Post 5 lbs South of 1/4 Sec corner bet Sec 5 & 8 a Pine 20 inches  
 Thence West
- 19 98 Set Post for 1/8 corner on South Edge SW 1/4 Sec 5  
 Thence North through center of 1/4 Sec 5
- 20 00 Set Temporary 1/6 corner  
 40 00 Set Temporary center of 1/4 Sec 5  
 60 00 Set Temporary 1/6 corner  
 79 50 The 1/8 corner on North Edge NW 1/4 Sec 5  
 The 1/4 Sec corner bet Sec 5 & 6  
 Thence East through Sec 5
- 40 00 Set Temporary center Sec 5  
 79 71 Intersect 12 lbs South of 1/4 Sec corner bet Sec 4 & 5  
 from which I marked a Pine 30 inch dia. bears N 57° 30' E 145 lbs distant  
 Thence West
- 59 71 The Center Sec 5