

Township 4 South Range 40 East Union County, Oregon.

CHAINS	LINKS	
40	18	Set Stone 7+8+14 inches for $\frac{1}{4}$ Sec corner bet Sec 5 & 8 The corner to Sec 5=8=17 & 18 Thence East $Var 20^{\circ} E$
39	94	found no $\frac{1}{4}$ Sec corner
80	36	Intersect 25 lks North of corner to Sec 8=9=16 & 17 a Post in $Var 20^{\circ} E$ Thence $N 89^{\circ} 49' W$ on True line
40	18	Set Post for $\frac{1}{4}$ Sec corner bet Sec 8 & 17 at a Point from which a Stone marked $\frac{1}{4}$ said to be set by Moses Austin County Surveyor in doing some work for John Hobins but left no record bears $N 2^{\circ} W$ 32 links distant Thence North through Sec 8 $Var 20^{\circ} 15' E$
40	47	Intersect True East & West line at center Sec 8
60	00	Set Temporary $\frac{1}{16}$ corner
80	75	The $\frac{1}{4}$ Sec corner bet Sec 5 & 8 Thence South on line
20	14	Set Stone 6+12+22 in mound of Stone for $\frac{1}{16}$ corner in center $N \frac{1}{2}$ Sec 8
40	00	The $\frac{1}{8}$ corner Point on North Boundary N $\frac{1}{4}$ Sec 8 Thence South
20	12	Set Stone 6+8+14 for $\frac{1}{16}$ corner in center $NW \frac{1}{4}$ Sec 8
40	25	Set Post for center $W \frac{1}{2}$ Sec 8
60	31	Set Stone 8+9+20 inch for $\frac{1}{16}$ corner in center $SW \frac{1}{4}$ Sec 8 The corner to Sec 5=6=7 & 8 Thence North $Var 20^{\circ} E$
40	00	found no $\frac{1}{4}$ Sec cor. Set Temporary $\frac{1}{4}$ Sec Post
80	90	Intersect North Boundary 67 lks East of corner to Sec 5=6=31 & 32 Thence South $29^{\circ} E$ on True line
40	60	Set 18+7+8 for $\frac{1}{4}$ Sec corner bet Sec 5 & 6
80	90	The corner to Sec 5=6=7 & 8 Thence West $Var 20^{\circ} E$
20	00	Set Temporary $\frac{1}{8}$ corner
40	24	The $\frac{1}{4}$ Sec corner bet Sec 6 & 7 a Stone Thence East
20	12	Set Stone 6+9+14 for $\frac{1}{8}$ corner W. Kinbell County Surveyor