

CHAINS.
LKS.

The corner to Sec 17 = 18 = 19 & 20
Thence South bet Sec 19 & 20
Var 20° E

40 38 The 1/4 Sec corner bet Sec 18 & 19
Thence South var 20° E

40 00 Intersect - E of W line 664 links west of
The corner to Sec 19 = 20 = 29 & 30
Thence N 8° 31' W on True line

40 50 The 1/4 Sec corner bet Sec 19 & 20

The corner to Sec 19 = 20 = 29 & 30
Thence West bet Sec 19 & 30
Var 20° 30' E

40 57 The 1/4 Sec cor bet Sec 19 & 30 a stone in mound of Stone
Thence West var 20° E

41 45 found no Sec corner but at
54 75 The corner to Sec 19 = 30 = 24 & 25

The 1/4 Sec corner bet Sec 18 & 19
Thence South through Sec 19
Var 19° E

20 00 Set Temporary 1/16 corner

40 00 Set Temporary Center Sec 19

81 20 Intersect South Boundary 605 lks west of 1/4 Sec Cor
Thence N 6° 18' W on True line

The 1/4 Sec corner bet Sec 19 & 20
Thence West through Sec 19
Var 20° E

20 00 Set Temporary 1/16 corner

37 98 Intersect True North & South line at center

90 20 Intersect West Boundary at the 1/4 Sec cor
Thence East

27 25 Set Post for 1/16 corner

from which

a Pine 10 inches bears North 251 lks. dist.

53 22 Set Stone 15 x 9 x 9 inches for center Sec 19

from which

a a Pine 12 inches bears N 47 3/4° W 179 lks. dist.

71 71 Set Post in mound of Stone from which

a Pine 14 inches dia. bears S 29° E 21 lks. dist.