

CHAINS.	LES.	
		The corner to S 34 48 16 39 1/2 40 E Thence North on Guide Meridian var 20° 15' E
40	00	found no 1/4 Sec corner
80	00	found no Sec corner Set temporary Thence North on same variation
40	00	found no 1/4 Sec corner
80	00	found no 1/4 Sec corner Set Temporary Corner to Sec 24 = 25 = 19 1/2 30 Thence North between Sec 24 & 19 var 20° 15' E
40	00	found no 1/4 Sec corner Set Temporary 1/4 Sec Co
80	72	The corner to Sec 18 = 24 = 18 1/2 19 Making an Excess of 24 lks to Each mile as Per U.S. Field Notes I therefore have a falling of 12 lks North to Each one Half mile Thence South on line
40	12	Set Stone 25 x 17 x 6 inches for 1/4 Sec corner bet Sec 24 & 19
80	24	Set Stone 25 x 12 x 7 inches for Corner to Sec 24 = 25 = 19 1/2 30
		The 1/4 Sec corner bet Sec 11 & 12 Thence South bet Sec 11 & 12 var 20° E
20	00	Grande Poudre river Offset 500 lks west Thence South on Offset line
22	00	Grande Poudre River 100 lks across Course East
40	20	Intersect E & W line previously run 464 lks west of first Temporary Stake for Cor. bet 11 = 12 = 13 1/2 14 Thence South on Offset on account of William Bush
40	00	Set Temporary 1/4 Sec corner 500 lks East of Offset line
80	00	Set back East 500 lks on line and Drove Temporary corner to Sec 13 = 14 = 23 1/2 24 Thence South var 20° E
40	00	found no 1/4 Sec corner
80	00	found no Sec corner Thence South on same variation
40	00	found no 1/4 Sec corner
80	00	found no Section corner Thence South var 20° E
40	00	found no 1/4 Sec corner