

Township 3 South

Range 39 East

Union County, Oregon.

- 81 20 The Corner to Sec 1-2-35 & 36 on spline bet 23 & 48
 Making an Excess of 120 lks over US Field Notes
 I therefore have a falling of $13\frac{2}{3}$ lks North $\frac{1}{2}$ mile
 to Each $\frac{1}{2}$ mile
 Thence North on line
- 79 64 The Corner to Sec 13-24-18 & 19-23 & 24
 Thence West bet Sec 13 & 24
 Var. 20° E.
- 39 82 found no $\frac{1}{4}$ Sec corner
- 79 64 found no Sec corner Set Temporary Corner to Sec 13-14-23 & 24
 Thence West on some variation
 and found Sec or $\frac{1}{4}$ Sec corner until I intersect Range line
 bet Ranges 38 & 39 at The Corner to Sec 18-19-23 & 24
 at which point I have an Excess of 93 lks over US field notes
 I therefore run East on line allowing $15\frac{1}{2}$ lks to Each
 mile and set Granite Boulder $20 \times 12 \times 9$ inches for
 Corner to Sec 13-14-23 & 24 marked with 1 notch on E & 3 notches
 on the South Side
 Thence North on line bet Sec 13 & 14
 Var 20° E
- 40 $13\frac{2}{3}$ Set Stone $6 \times 12 \times 17$ inches for $\frac{1}{4}$ Sec corner bet Sec 13 & 14 in Road
- 80 $27\frac{1}{3}$ Set Stone $25 \times 10 \times 5$ inches on South Side of Slough for the
 Corner to Sec 11-12-13 & 14

J. W. Kimbrell County Surveyor

James Hendershott Chairman
 William Peck