

Township

Range

Union County, Oregon.

and 11 lks Thence $N 66^{\circ} 15' W$ 28 Rods and 6 lks To The Center
of Grande Round River Thence $S 20^{\circ} W$ 22 Rods
Thence $S 35^{\circ} W$ 34 Rods Thence South $20^{\circ} W$ 14 Rods
Thence $S 10^{\circ} W$ 59 Rods To Sec line bet Sec 10 & 15 - in
Center of Grand Round river Thence East on Sec line 104
Rods to The Sec corner to Sec 10 = 11 = 14 & 15

I then proceeded to Establish Witness Corners to
a Fractional Tract of Land in SW/4 Sec 11 as follows
To wit Lot No. 2

Commencing at a Point 52 Rods and 20 lks South of the
Center Sec 11 on right-Bank of Grande Round River Set Stone
6 x 8 x 14 marked M. 1 from which

a willow 3 inches dia bears $N 28^{\circ} 35' E$ 21 lks dist.

The True Corner being 4 Rods North of Stone in Center of river

Thence $S 55^{\circ} W$ 12 Rods a Stone marked M. 2 The True
Corner being 2 Rods North of Stone in Center of river

Thence $S 67^{\circ} W$ 37 Rods a Stone marked M. 3, The True
Corner being 2 Rods NW of Stone in Center of river

Thence $S 2^{\circ} E$ 10 Rods a Stone marked M. 4, The True
Corner being 2 Rods SW of Stone in Center of river

Thence $S 50^{\circ} 30' E$ 56 Rods a Stone marked M. 5, The True
Corner being 4 Rods South of Stone in Center of river

Thence from witness Corner North $var 20^{\circ} E$
64 Rods to Corner No 1 of Lot No. 2.

J. W. Fairbairn County Surveyor