

CHAINS.	LINKS.	
		Hence North bet Sec 7 & 8
39	95	Set Post for Corner to Sec 5-6-7 & 8 Hence North bet Sec 5 & 6
39	95	Set Post in John Carr's Garden for 1/4 Sec Cor bet Sec 5 & 6 The 1/4 Sec Corner bet Sec 7 & 8 Hence South bet Sec 7 & 8 Per 20° E
20	00	Set Temporary 1/8 Corner
39	77	The corner to Sec 7-8-17 & 18 in Center of County Road. Hence North
19	88 1/2	Set Post for 1/8 Corner
39	77	The 1/4 Sec cor bet Sec 7 & 8. I retraced the line bet Sec 6 & 7 and find it to be 7820 chains 20 lks over US field Notes The Corner to Sec 5-6-7 & 8 Hence East bet Sec 5 & 8 Per 20° E
20	00	Set Temporary 1/8 corner
40	00	I found The Old 1/4 Sec corner Post decayed Reestablished by planting a Stone 23 x 8 x 6 for 1/4 Sec Corner bet 5 & 8 Hence West
20	00	Set Stone 13 x 7 x 6 for 1/8 Corner The 1/4 Sec corner bet Sec 5 & 8 Hence East Per 20° E
40	10	found no Sec Corner Set Temporary cor to Sec 4-5-8 & 9 Hence East Per 20° E
40	35	The 1/4 Sec Corner bet Sec 4 & 9 Post decayed deposited Point of Old Stake and Drove New Stake 3 inches in diameter and 30 inches long in Old Mound along Side of Point of Old Stake The corner being in a Meadow I drove The Stake down Level with top of Ground Hence East bet Sec 4 & 9
40	00	found no Sec Corner Set Temporary cor to Sec 3-4-9 & 10 Hence East bet Sec 3 & 10 Per 20° E
40	13	Rail fence Course N & S