

CHAINS	LINKS	
46	65	Grande Round river 119 Mts across Course South
79	45	The Corner to Sec 2=3=10 & 11 Thence South bet Sec 10 & 11 Dev 20° E
15	11	Grande Round River 140 Mts across Course East
40	18	The 1/4 Sec corner bet Sec 10 & 11 The Corner to Sec 3=4=33 & 34 Thence South bet Sec 3 & 4 Dev 20° E
1	05	Grande Round River 177 Mts across Course East
39	66	found no 1/4 Sec corner Set Temporary 1/4 Sec corner bet 3 & 4
79	66	Intersect E & W line at first Temporary Cor. Thence South bet Sec 9 & 10 Dev 20° E
		But found no corner until I intersect E & W line at the corner to Sec 27=28=33 & 34 The distance corresponding with U.S. Field Notes Thence West bet Sec 28 & 33 Dev 20° E
80	00	The Corner to Sec 28=29=32 & 33 Thence North bet Sec 28 & 29
40	00	found no 1/4 Sec corner
80	50	Rail fence on South Side County Road
81	80	wire fence Continue North and find no 1/4 Sec or Sec corner as per U.S. Field Notes 3 miles and Set Temporary Corner to Sec 8=9=16 & 17 Thence North bet Sec 8 & 9 Dev 20° E
40	00	found no 1/4 Sec corner Set Temporary 1/4 Sec corner
80	00	Intersect E & W line 25 Mts East of 1st Temporary Station Thence North bet Sec 4 & 5 Dev 20° E
40	00	Set Temporary 1/4 Sec corner
78	82	Intersect North Boundary of Township at the corner to Sec 4=5=32 & 33 Thence South bet Sec 4 & 5
39	75	Set Stone 8x12x24 inches for 1/4 Sec corner bet Sec 4 & 5
79	65	Set Stone 19x12x8 inches for corner to Sec 4=5=8 & 9