

RECORD OF SURVEY

102
1888

Township 3 South

Range 39 East

Union County, Oregon.

CHAINS.	LINKS.	
		Thence South bet Sec 8 & 9 Var 20° E
39	90	Set Stone 20 x 10 x 7 inches for 1/4 Sec Corner bet Sec 8 & 9
59	85	Set Stone 23 x 10 x 5 for 1/8 corner
79	80	The Corner to Sec 8 = 9 = 16 & 17
		The Corner to Sec 7 = 8 = 17 & 18
		Thence East bet Sec 8 & 17 Var 20° E
40	20	found no 1/4 Sec Corner set Temporary 1/4 Sec on
80	40	The Corner to Sec 8 = 9 = 16 & 17
		Thence East
20	10	Set Temporary 1/8 corner
80	42	found no Corner to Sec 9 = 10 = 15 & 16
		Thence East
80	65	The Corner to Sec 10 = 11 = 14 & 15 —
		Making an excess of 47 lks and a falling of 16 lks to each mile
		The 1/4 Sec corner bet Sec 3 & 4
		Thence West through Sec 4 Var 20° E
40	21	Set Temporary Center Sec 4
80	30	The 1/4 Sec Corner bet Sec 4 & 5 —
		The 1/4 Sec corner bet Sec 4 & 9
		Thence North through Sec 4
20	00	Set Temporary 1/6 corner
39	87	Intersect E & W line at Center Sec 4 set Stone 6 x 12 x 22 for Center Sec 4
		Thence South
19	93	Set Stone 6 x 16 x 21 for 1/6 corner in center S 1/2 Sec 4
		Thence West
20	09	Set Stone 6 x 10 x 26 for 1/6 corner in center S W 1/4 Sec 4
		Thence South
19	96	Set Stone 8 x 6 x 24 in for 1/8 corner on South Boundary S W 1/4 Sec 4
		The North Body S W 1/4 Sec 4
		Set Stone 6 x 6 x 15 for 1/6 corner in center W 1/2