

- The 1/4 sec corner set Sec 5 1/2 8
 Thence South through Sec 8 Var 20° E
- 40 00 Set temporary center Sec 8
 60 00 Set temporary 1/16 corner
 80 05 Intersect South Boundary Sec 8 7 1/2 E of 1/4 Sec corner set Sec 8 1/2 17
- The 1/4 Sec Corner set Sec 8 1/2 9
 Thence West through Sec 8 Var 20° E
- 40 28 Intersect True N 1/2 S line 3 1/2 Sec South of first Stake for center
 80 37 Intersect West Boundary at 1/4 Sec corner set Sec 8 1/2 9
 Thence East
- 40 09 Set Stone 6 x 12 x 18 for Center Sec 8
- The 1/8 Corner on West Boundary S W 1/4 Sec 8
 Thence East Var 20° E
- 40 27 Set Stone 7 x 12 x 23 inches for 1/16 corner in Center S 1/2 Sec 8
 80 42 Intersect East Boundary Sec 8 at 1/8 corner on E Bdy S E 1/4 Sec 8
 Set Stone 6 x 10 x 23 inches for 1/8 corner
 Thence East
- 20 25 Set Stone 6 x 13 x 20 inches for 1/16 corner in Center S W 1/4 Sec 9
- The 1/4 Sec Corner set Sec 5 1/2 3 E
 Thence South through Sec 5
 Var 20° E
- 3 70 Slough of Grande Round River 148 1/2 Sec across Course East
 39 36 Set temporary center Sec 5
 77 73 Intersect South Boundary at 1/4 Sec corner set Sec 5 1/2 8
- The 1/4 Sec Corner set Sec 5 1/2 6
 Thence East through Sec 5 Var 20° E
- 20 00 Set temporary 1/16 corner
 40 07 Intersect N 1/2 S line at first Stake for center
 80 38 Intersect East Boundary at 1/4 Sec corner set Sec 4 1/2 5
 Thence West
- 40 30 Set Stone 6 x 10 x 18 inches for center Sec 5
 60 30 Set Stone 7 x 12 x 18 for 1/16 corner in Center W 1/2 Sec 5
- The 1/8 corner on South Boundary S W 1/4 Sec 5
 Thence North through W 1/2 Sec 5 Var 20° E
- 39 82 Center W 1/2
 78 30 Slough 127 1/2 Sec across course N 8
 74 57 1/2 corner on N Bdy N W 1/4 Sec 5 on left bank of Slough