

Township 6 South

Range 38 East

Union County, Oregon.

- 80 84 the corner to Sec 26=27=34 & 35 under Hay Stack  
Thence South
- 40 41 the 1/4 Sec corner bet Sec 34 & 35—  
Thence North
- 40 41 the corner to Sec 26=27=34 & 35— under Hulehinsens Hay Stack  
Thence  $N 2^{\circ} 00'$  bet Sec 26 & 27  
Var  $20^{\circ} E$
- 40 41 Set Stake under the ground & Stone marked 1/4 for 1/4 Sec corner bet Sec 26 & 27  
Thence  $W 10^{\circ} E$  through Sec 27  
Var  $10^{\circ} E$
- 40 00 Set Temporary Center Sec 27
- 78 00 Intersect  $N \frac{1}{2} S$  line 60 lts. West of 1/4 Sec corner bet Sec 27 & 28—
- The 1/4 Sec corner bet Sec 27 & 34.  
Thence  $N 1^{\circ} 20'$  Var  $20^{\circ} E$
- 40 20 Intersect True  $E \frac{1}{2} W$  line 15 lts East of first Stake for Cent
- 82 70 Intersect North Boundary 90 lts East of the 1/4 Sec cor bet Sec 22 & 27  
Thence  $S 2^{\circ} 18' E$  on true line
- 82 70 Set Stone 20 x 18 x 14 inches for Center Sec 27

J. W. Kimbrell County Surveyor