

RECORD OF SURVEY
No. 54

Township 3 South Range 37 East 10 M. Union County, Oregon.

George Beckler Nov. the 15th 1888

CHAINS
LINKS

I Commenced at the 1/4 Sec corner
bet Sec 19 & 20 on Range line
bet Ranges 37 & 38

Thence South bet Sec 19 & 24
Var 20° E

40 00 The corner to Sec 24 = 25 = 19 & 30
a Post in Mound of Stone
Thence South bet Sec 25 & 30

20 00 Set temporary 1/8 corner

40 30 Intersect the 1/4 Sec corner bet Sec 25 & 30
Thence North

20 15 Set Post in Mound of Stone for
1/8 corner on East side of 1/4 Sec 25 -

The 1/4 Sec corner bet Sec 25 & 30
Thence west through Sec 25 -
Var 20° E

40 00 Set temporary center Sec 25 -

81 80 Intersect 1/5 Mls South of 1/4 Sec
corner bet Sec 25 & 26
Thence S 89° 41' E on Line line

40 90 Marked a Fir tree 11 inches diameter for Center Sec 25 -
Thence North

38 50 The 1/4 Sec corner bet Sec 24 & 25 -
Thence North

19 25 Set Post in Mound of Stone for 1/16 corner in Center N 1/4 Sec 24
The 1/4 Sec corner bet Sec 24 & 25 -
Thence East

39 40 The corner to Sec 24 = 25 = 19 & 30
Thence west

19 70 Set Post in Mound of Stone for 1/8 corner on Side S 1/4 Sec 24
The 1/4 Sec corner bet Sec 24 & 19
Thence west through Sec 24 Var 20° E

80 30 Intersect 25 Mls North of 1/4 Sec corner bet Sec 25 & 30
Thence N 89° 50' E on Line line

60 21 Set Post for center 1/2 Sec 24 from which
a Fir 6 inches dia. bears N 38° 10' 56" E 148 ft
" 20 " " " " S 32° E 148 " " "

