

CHAINS LKS Thence South through Sec 15 var 20° E  
40 83 Intersect E & W line 21 1/2 m East of first State Center

81 85 Intersect South Boundary 192 M West of 1/4 Sec Corner  
bet Sec 15 & 22 a Pine 18 inches dia N 10° W 97 lks  
" 24 " " 87° W 99 "

Thence North 1° 23' W on true line  
40 92 Set Post marked C.S. for Center Sec 15-

The 1/4 Sec corner bet Sec 21 & 22

from which  
a Pine 14 inches dia. bears N 88° E 35 M dist.  
fir 12 " " " S 13° W 76 " "

Thence East through Sec 22

80 83 Intersect East Boundary 77 M South of 1/4 Sec Corner bet Sec 21 & 22

from which a Pine  
a Pine 22 inch dia. bears N 74° E 141 M dist.  
" 30 " " " N 65° W 370 " "

Thence S 89° 27' W on true line

60 62 Set Post for 1/16 corner in Center of Sec 22

from which  
a Pine 14 inch dia. bears N 13° E 68 M dist.  
sawrack 8 " " " 87° E 72 " "

The Corner to Sec 15-16-21 & 22

Thence West bet Sec 16 & 21 var 20° E

20 00 Set temporary 1/8 corner

40 52 The 1/4 Sec corner bet Sec 16 & 21

Thence East

20 26 Set Post for 1/8 corner

from which  
a fir 7 inches dia bears N 85° W 109 lks dist  
" 7 " " " S 67° E 125 " "

40 52 The corner bet Sec 15 & 16 & 21 & 23

The 1/4 Sec corner bet Sec 21 & 16

from which  
a Pine 24 inches dia bears S 78° E 25 lks dist  
" 20 " " " N 31° E 88 " dist

Thence North through Sec 16

var 20° E

82 29 Intersect North Boundary Sec 16

600 M East of 1/4 Sec corner bet Sec 9 & 16