

1898

Township 3 South

Range 36 East

Union County, Oregon.

CHAINS. LKS.

20 31 Hence East through  $N 8^{\circ} 14'$  Sec 26  
 Set Post for  $1/16$  corner in cuts  $N 8^{\circ} 14'$  Sec 26  
 from which  
 a Pine 10 inches diameter  $S 46^{\circ} E$  30 lks dist  
 " 14 " " " "  $N 42^{\circ} W$  150 " "

The  $1/4$  Sec corner bet Sec 25 & 26  
 Hence East through Sec 25 -  
 Var  $20^{\circ} E$

40 00 Set temporary  $1/16$  corner  
 40 50 Set temporary center Sec 25 -  
 60 00 Set temporary  $1/16$  corner  
 79 91 Intersect East boundary 71 lks South of

The  $1/4$  Sec corner bet Sec 25 & 30  
 from which  
 a fir 24 inches dia  $N 40^{\circ} W$  29 lks  
 " 20 " " " "  $N 52^{\circ} E$  53 "  
 Hence South  $89^{\circ} 35' W$  on true line  
 through Sec 25 -

The  $1/4$  Sec corner bet Sec 25 & 30  
 Hence North bet Sec 25 & 30  
 Var  $20^{\circ} E$

40 72 Intersect 75 lks East of corner to Sec 24 = 25 = 19 & 30  
 from which  
 a Pine 34 inches dia,  $S 74^{\circ} W$  68 lks dist  
 " 32 " " " "  $S 12^{\circ} E$  106 " "  
 " 33 " " " "  $N 41^{\circ} W$  29 " "  
 " 32 " " " "  $N 5^{\circ} E$  80 " "  
 Hence West bet Sec 24 & 25 -  
 Var  $24^{\circ} E$

20 50 Set temporary  $1/8$  corner  
 39 26 The  $1/4$  Sec corner bet Sec 24 & 25 -  
 from which  
 a Pine 28 inches dia,  $S 83^{\circ} W$  276 lks dist  
 " 34 " " " "  $N 73^{\circ} W$  289 " "

Hence East  
 19 63 Set Post for  $1/8$  corner  
 39 26 The corner to Sec 24 = 25 = 19 & 30