

CHAINS. LKS.

The 1/4 Sec corner bet Sec 13 & 14  
Thence North through Sec 13  
for 20° E

82 88 Intersect E of W line 190 lks west of the 1/4 Sec cor bet Sec 13 & 14  
Thence South 1° W on true line

20 57 Set Post for 1/16 corner in Center of Sec 13

41 15 Set Post for Center Sec 13

from which

a Pine 25 inches dia, bearing S 29° E 212 lks dist.

" 23 " " " S 31° W 261 " "

62 01 Set Post for 1/16 corner in Center of Sec 13

from which

a Pine 14 inches dia, bearing S 44° E 67 lks dist.

" 14 " " " S 67° W 184 " "

" 24 in " " N 23° W 330 " "

82 88 The 1/4 Sec corner bet Sec 13 & 14

The center Sec 13

Thence West

20 41 Set Post for 1/16 corner in Center of Sec 13

from which

a Pine 12 inch dia bearing S 79° E 154 lks dist.

" 12 " " " N 62° W 83 " "

Thence North through NW 1/4 Sec 13

41 00 The 1/8 corner on North Boundary N W 1/4 Sec 13

Thence South

20 50 Set Post for 1/16 corner in Center N W 1/4 Sec 13

41 00 The 1/16 corner in Center W 1/2 Sec 13

Thence South

41 31 The 1/8 corner on South Boundary S W 1/4 Sec 13

Thence North

20 65 Set Post for 1/16 corner in Center S W 1/4 Sec 13

from which

a Pine 18 inches dia, bearing S 47° E 334 lks dist.

41 31 The 1/16 corner in Center W 1/2 Sec 13

The center Sec 13

Thence East

20 04 Set Post for 1/16 corner in Center E 1/2 Sec 13

Thence South through

The S E 1/4 Sec 13