

CHAINS. LKS.

80 52 The corner to Sec 19=20=29 & 30  
from which I run North on line  
bet Sec 19 & 20 var 20° E

40 25 Set Stone 6 x 9 x 16 for 1/4 Sec corner bet Sec 19 & 20

80 50 Set Stone 8 x 9 x 20 inch for corner to Sec 17=18=19 & 20  
thence East bet Sec 17 & 20  
var 20° E

39 85 Set Temporary 1/4 Sec corner

79 70 found no corner Set Temporary corner to Sec 16=17=20 & 21

39 57 found no 1/4 Sec corner

79 14 found no corner to Sec 15=16=21 & 22  
thence East

11 00 Grande Round River 250 lks across course N 10° W

42 25 Intersect the 1/4 Sec corner bet Sec 15 & 22  
thence West allowing 32 lks excess  
to back 1/2 mile over U.S. field note  
to corner to Sec 16=17=20 & 21  
thence West

40 17 Set Stone 6 x 8 x 18 for 1/4 Sec corner bet Sec 17 & 20

80 34 The corner to Sec 17=18=19 & 20

The corner to Sec 19=20=29 & 30  
thence East bet Sec 20 & 29  
var 20° E

20 11 The 1/8 corner on South Boundary SW 1/4 Sec 20

40 00 Set Temporary 1/4 Sec corner

60 00 Set Temporary 1/8 corner

71 00 Grande Round River 347 lks across under Halls  
Bridge course of River N. 20° E

80 38 To the corner to Sec 20=21=28 & 29  
thence West

20 09 Set Stone 6 x 10 x 20 inch for 1/8 corner

40 18 Set Stone 6 x 9 x 22 in for 1/4 Sec corner bet Sec 20 & 29

60 27 The 1/8 corner

80 38 The corner to Sec 19=20=29 & 30

The 1/4 Sec corner bet Sec 19 & 20 thence East

80 20 The 1/4 Sec corner bet Sec 20 & 21 thence West

20 05 Set Stone for 1/16 corner

40 10 Set Stone for center Sec 20

60 15 Set Stone for 1/16 corner

80 20 The 1/4 Sec corner bet Sec 19 & 20

40 22 The center Sec 20  
80 45 The 1/4 Sec corner bet Sec 20 & 29  
W. Kimball County Survey 5