

- 41 06 The $\frac{1}{4}$ Sec Corner bet Sec 31 & 32
making an Excess of 106 lbs as per US Field Notes
thence North var $19^{\circ} 30' E$.
- 40 21 Set Post for Temporary corner to Sec 29 = 30 = 31 & 32
thence North bet Sec 29 & 30 var $18^{\circ} 45' E$
- 40 21 Set Stake for $\frac{1}{4}$ Sec Corner
- 80 42 Set Post for Corner to Sec 19 = 20 = 29 & 30
thence North bet Sec 19 & 20
var $19^{\circ} E$
- 40 21 Set Stake for $\frac{1}{4}$ Sec Corner bet Sec 19 & 20
- 80 42 The corner to Sec 17 = 18 = 19 & 20
- The $\frac{1}{4}$ Sec corner bet Sec 20 & 29
thence North through Sec 20
- 33 50 Set Temporary fractional corner
- 40 05 Set Temporary center Sec 20.
- 60 22 Set Temporary $\frac{1}{16}$ corner
- 80 32 The $\frac{1}{4}$ Sec corner bet Sec 17 & 20
thence South
- 20 08 Set Stone 8 x 8 x 18 for $\frac{1}{16}$ corner in center $\frac{1}{4}$ Sec 20
- 40 16 The center Sec 20
- 50 26 Set Stone 6 x 9 x 22 for fractional corner bet Olin & Loyde
- The $\frac{1}{4}$ Sec corner bet Sec 19 & 20
thence East through Sec 20
- 40 31 Intersect N & S line at center Sec 20
- 80 78 The $\frac{1}{4}$ Sec corner bet Sec 20 & 21

Note

The Point for corner to Sec 19 = 20 = 29 & 30 which I determined by proportional measurement from known corner to known corner E & W N & S, is in dispute by some of the settlers as to the point East and West and think they can prove the original location to be about 120 lbs west. But as I have retraced the whole distance E & W from Range line to Range line and find the excess to be the same as it is bet Sec 20 & 29 and 19 & 30 57 lbs to each mile over the US Field Notes showing conclusively that the chaining was done about the same throughout the Township.

W. H. Kimbell County Surveyor