

CHAINS	LKS.	
		Thence North bet Sec 31 & 32
80	00	found no Sec corner Set temporary corner to Sec 29=30=31 & 32 Thence North bet Sec 29 & 30 Var 20° E
35	67	Grande Round River 248. lks across Course S.W.
80	00	Set temporary corner to Sec 19=20=29 & 30 Thence North bet Sec 19 & 20 Var 20° E
40	00	Set temporary 1/4 Sec corner
80	00	Set temporary corner to Sec 17=18=19 & 20 Thence North bet Sec 17 & 18 Var 20° E
40	00	found no 1/4 Sec corner
81	63	Intersect 78 lks west of the corner to Sec 7=8=17 & 18 making an excess of 163 lks as per U.S. Field Notes Thence South 8 1/4 West
80	39	Set Stone 10 x 12 x 20 for corner to Sec 17=18=19 & 20 Thence South bet Sec 19 & 20
40	20	Set Stone 9 x 10 x 18 for 1/4 Sec Cor. bet Sec 19 & 20
80	40	Set Stone 10 x 11 x 25 for corner to Sec 19=20=29 & 30
		The 1/4 Sec corner bet Sec 16 & 21 Thence South through Sec 21 Var 20° E
79	68	The 1/4 Sec corner bet Sec 21 & 28 Thence North through center Sec 21
19	92	Set Stone 10 x 12 x 23 for 1/6 corner in center S 1/2 Sec 21
39	84	Set Stone 9 x 12 x 24 for center Sec 21
59	76	Set Stone 8 x 12 x 18 for 1/6 corner in center N 1/2 Sec 21
		The 1/4 Sec corner bet Sec 20 & 29 Set Stone 8 x 10 x 24 for 1/4 Sec corner bet Sec 20 & 29 Thence North through Sec 20
40	00	Set temporary center Sec 20
80	41	The 1/4 Sec corner bet Sec 17 & 20 Set Stone 9 x 10 x 20 for 1/4 Sec corner bet Sec 17 & 20
		The 1/4 Sec corner bet Sec 20 & 21 Thence West through Sec 20
40	36	Set Stone 9 x 10 x 80 for center Sec 20
80	49	The 1/4 Sec corner bet Sec 19 & 20