

No 78

Township 8 South

Range 46 East W.M.

Union County, Oregon.

John Erickson

May the 30th 1889

I Commenced at the 1/4 Sec cor.
bet Sec 18 & 24

from which

a Cottonwood 8 in bro N 10° E 342 lks dist

a Poplar 6 " " S 50° W 442 " "

Thence North through Sec 18
over 20° E

17 57 Pine Creek 114 lks across course S 50° E

20 50 Set temporary 1/6 corner

40 50 Set temporary center Sec 18

80 24 Intersect - 12 lks East of the 1/4 Sec
corner bet Sec 12 & 18

The corner to Sec 18 = 24 = 18 & 19

on Range line bet Ranges 46 & 47 East

Thence North on Range line
bet Sec 18 & 18
over 20° E

40 00 found no 1/4 Sec corner

Set temporary 1/4 Sec corner

41 70 Pine Creek 184 lks across course East

79 10 The corner to Sec 12 = 18 = 7 & 18

Thence South

39 55 Set Post for 1/4 Sec corner bet Sec 18 & 18 in wood of trees

from which

a Pine 18 inches dia bro N 18° E 110 lks dist

maple 5 " " " S 40° W 80 " "

59 32 Set Post for 1/8 corner

79 10 The corner to Sec 18 = 24 = 18 & 19

The 1/4 Sec corner bet Sec 18 & 14

Thence East through Sec 18

over 25° E

40 43 Intersect - True N & S line 20 lks North of first Stake for center

74 87 Pine Creek 173 lks across course N 10° E

80 45 Intersect East Boundary 120 lks North of 1/4 Sec cor bet Sec 18 & 18

Thence N 89° 8' W on True line

40 02 The center Sec 18

