

Township 8 South

Range 46 East

Union County, Oregon.

| CHAINS | LINKS | |
|--------|-------|---|
| | | The center Sec 18 |
| | | Thence South through center $S \frac{1}{2}$ Sec 18 |
| 19 | 80 | Set Post for $\frac{1}{16}$ corner in center $S \frac{1}{2}$ Sec 18 from which an asp 6 inches dia. brs $S 76^{\circ} W 48$ lks dist " 18 " " " $S 50 \frac{1}{2}^{\circ} E 92$ " " |
| | | Thence East through $S \frac{1}{4}$ |
| 11 | 68 | Pine creek 227 lks across course $N 20^{\circ} E$ |
| 20 | 00 | Set temporary $\frac{1}{16}$ corner |
| 40 | 26 | The $\frac{1}{2}$ corner on East Boundary $S \frac{1}{4}$ Sec 18 |
| | | Thence West |
| 20 | 13 | Set Post in Edg of Slough for $\frac{1}{16}$ corner in center $S \frac{1}{4}$ Sec 18 from which an asp 8 inches dia brs $S 38^{\circ} E 42$ lks dist " 6 " " " $S 82^{\circ} W 90$ " " |
| | | The $\frac{1}{4}$ Sec corner bet Sec 18 & 24 |
| | | Thence East bet Sec 18 & 24 Var $20^{\circ} E$ |
| 20 | 00 | Set temporary $\frac{1}{8}$ corner |
| 40 | 14 | Intersect 44 lks South of Corner to Sec 18 = 24 = 18 & 19 Thence $S 89^{\circ} 22' W$ on true line |
| 20 | 17 | Set Post in Mound of Stones for $\frac{1}{8}$ corner |
| 40 | 14 | The $\frac{1}{4}$ Sec corner bet Sec 18 & 24 Thence South through Sec 24 Var $20^{\circ} E$ |
| 20 | 00 | Set temporary $\frac{1}{16}$ corner |
| 40 | 00 | Set temporary Center Sec 24 |
| 80 | 46 | Intersect 5 lks East of $\frac{1}{4}$ Sec corner bet Sec 24 & 25 |
| | | The $\frac{1}{4}$ Sec corner bet Sec 28 & 24 from which a $\frac{1}{2}$ glaze 12 inches dia brs West 120 lks dist Thence East through Sec 24 Var $20^{\circ} E$ |
| 20 | 00 | Set temporary $\frac{1}{16}$ corner |
| 40 | 20 | Intersect True N & S line 8 lks South of intersection |
| 60 | 00 | Set temporary $\frac{1}{16}$ corner |
| 82 | 25 | Intersect East Boundary 8 lks South of $\frac{1}{4}$ Sec corner bet Sec 24 & 25 Thence $S 89^{\circ} 57' W$ on true |