

RECORD OF SURVEY

Township 3 South

Range 38 East

Union County, Oregon.

The corner to Sec 1 = 6 = S 1 1/4 Sec 6

Hence South set sec 1 1/4 6.

Var 20° E

29 53 Set temporary 1/8 corner

40 16 Intersect 37 lks East of the 1/4 Sec corner set sec 1 1/4 6
from whicha Pine 24 inches ~~dia.~~ frs 885° E 168 lks dist

Hence N 41° 32' E on true line

20 08 Set post for 1/8 corner

40 10 The corner to Sec 1 = 6 = S 1 1/4 Sec 6

The 1/4 sec corner set sec 5 1/4 6

Hence west through sec 6 Var 20° E

7 20 Rail road S E 1/4 N W

14 35 creek S E

20 03 Set temporary 1/16 corner

35 23 Wire fence N 1/2 S

40 24 Intersect true N 1/2 S line

The 1/8 corner on East Boundary N 8 1/4 Sec 6

Hence west through N 1/4 Sec 6 Var 20° E

9 65 Creek 10 lks across course south

20 53 Set temporary 1/16 corner

29 25 Rail road N W 1/4 S E

33 42 Picket fence N 1/2 S A Gangtoff's Orchard and Garden

34 87 Picket fence N W 1/4 S E leave Garden & orchard

40 14 Intersect true N 1/2 S line

78 59 The 1/8 corner on West Boundary N W 1/4 Sec 6

Hence East through center N 1/4 Sec 6

38 59 Set stone 6 x 10 x 28 for 1/16 corner in center N 1/4 Sec 6

58 66 The center N E 1/4 Sec 6

78 59 The 1/8 corner on East Boundary N E 1/4 Sec 6

The 1/16 corner in Center E 1/4 Sec 6

Hence North through E 1/4 Sec 6

39 68 Intersect 19 lks East of corner on North Bdy N E 1/4 Sec 6

Hence S 16° E on true line

19 84 Set stone 6 x 9 x 17 for 1/16 corner in center N E 1/4 Sec 6

W. L. Turner 1900